

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338 (113 & 114) R-5	WILL	525	8
STA. TO STA.		FAP 338 (IL RTE. 59)	
FED. ROAD DIST. NO.	ILLINOIS		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	TRAFFIC SIGNALS IL 59 @ FRASER 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY Y031-1F	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	WATER MAIN/ SANITARY SEWER 100% VILLAGE Y060	SIDEWALK 50% STATE 50% VILLAGE SFTY-10
55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	190	190								
55034700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 53, RISE 34	FOOT	325	325								
55037600	STORM SEWERS TO BE CLEANED 8"	FOOT	74	74								
55037800	STORM SEWERS TO BE CLEANED 12"	FOOT	432	432								
55037900	STORM SEWERS TO BE CLEANED 15"	FOOT	429	429								
55038000	STORM SEWERS TO BE CLEANED 18"	FOOT	1,306	1,306								
55038200	STORM SEWERS TO BE CLEANED 24"	FOOT	312	312								
55038400	STORM SEWERS TO BE CLEANED 30"	FOOT	128	128								
55038700	STORM SEWERS TO BE CLEANED 42"	FOOT	670	670								
* 55100300	STORM SEWER REMOVAL 8"	FOOT	30	30								
* 55100400	STORM SEWER REMOVAL 10"	FOOT	65	65								
* 55100500	STORM SEWER REMOVAL 12"	FOOT	540	540								
* 55100700	STORM SEWER REMOVAL 15"	FOOT	424	424								
* 55100900	STORM SEWER REMOVAL 18"	FOOT	1,120	1,120								
* 55101200	STORM SEWER REMOVAL 24"	FOOT	235	235								
* 55101400	STORM SEWER REMOVAL 30"	FOOT	248	248								
* 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	1,730								1,730	
* 56103510	DUCTILE IRON WATER MAIN 20"	FOOT	3,020								3,020	
56400100	FIRE HYDRANTS TO BE MOVED	EACH	16								16	
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	19								19	
* 60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	24,475	24,475								
60200105	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1								
60200805	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 8 GRATE	EACH	11	11								
60201320	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	35	35								

- ▲ Non-Participating
- * SPECIAL PROVISION
- SPECIALITY ITEM
- ∞ CONSTRUCTION CODE Y080

VILLAGE = VILLAGE OF PLAINFIELD
 COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
 DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
 DATE MARCH 18, 2008
 DRAWN BY JMH
 CHECKED BY JCM