

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	12
STA.		TO STA.		
FED. ROAD DIST. NO.		PLANET		
		FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ FRASER	TRAFFIC SIGNALS IL 59 @ RENWICK	TRAFFIC SIGNALS IL 59 @ FORT BEGGS	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/ SANITARY SEWER	SIDEWALK
				80% FED 20% STATE	80% FED 10% STATE 10% VILLAGE	80% FED 10% STATE 10% COUNTY	80% FED 13.3% STATE 6.7% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	100% VILLAGE	50% STATE
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SFTY-1B
O *	78008270 POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	665	665								
O	78100100 RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,110	1,110								
O	78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16	16								
O *	78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,422	1,422								
O	78200100 MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	139	139								
	78300100 PAVEMENT MARKING REMOVAL	SQ FT	18,394	18,394								
O	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	270	270								
O	81000600 CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	6,652		508	488	605	5,051				
O	81000700 CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	322		32	82	208					
O	81000800 CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	38		38							
O	81001000 CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	60		10	34	16					
O	81018500 CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	799		110	49	78	562				
O	81018700 CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	146		146							
O	81018800 CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	68		68							
O	81018900 CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	606		104	324	180					
O	81400100 HANDHOLE	EACH	22		4	6	4	8				
O	81400200 HEAVY-DUTY HANDHOLE	EACH	9		4	4	1					
O	81400300 DOUBLE HANDHOLE	EACH	4		2	1	1					
O	81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7,205		583	813	758	5,051				
O *	85000200 MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1					1				
O *	85700205 FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3		1	1	1					
O	86400100 TRANSCEIVER - FIBER OPTIC	EACH	3		1	1	1					
O	87301215 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,676.5		969	382	325.5					
O	87301225 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,104.5		1,374	770	674.5			286		
O	87301245 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,653		809	856	988					

* SPECIAL PROVISION

O SPECIALITY ITEM

∞ CONSTRUCTION CODE Y080

VILLAGE = VILLAGE OF PLAINFIELD

COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM