

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	14
STA.		TO STA.		
FED. ROAD DIST. NO.		MILEAGE		
		FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ FRASER	TRAFFIC SIGNALS IL 59 @ RENWICK	TRAFFIC SIGNALS IL 59 @ FORT BEGGS	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/ SANITARY SEWER	SIDEWALK
				80% FED 20% STATE	80% FED 10% STATE 10% VILLAGE	80% FED 10% STATE 10% COUNTY	80% FED 13.3% STATE 6.7% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	100% VILLAGE	50% STATE 50% VILLAGE
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SFTY-1B
O	88102740 PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	2				1	1				
O	88200100 TRAFFIC SIGNAL BACKPLATE	EACH	12				8	4				
O	88200210 TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10							
O	88500100 INDUCTIVE LOOP DETECTOR	EACH	29		10	12	7					
O	88700200 LIGHT DETECTOR	EACH	6							6		
O	88700300 LIGHT DETECTOR AMPLIFIER	EACH	3							3		
O	88800100 PEDESTRIAN PUSH-BUTTON	EACH	8		2	3	3					
O	89000100 TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2			1	1					
O	89502200 MODIFY EXISTING CONTROLLER	EACH	1					1				
O *	89502375 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2				1	1				
O *	89502380 REMOVE EXISTING HANDHOLE	EACH	19				10	5	4			
O *	89502385 REMOVE EXISTING CONCRETE FOUNDATION	EACH	12				9	3				
*	Z0001050 AGGREGATE SUBGRADE 12"	SQ YD	104,624	104,624								
▲ *	Z0018500 DRAINAGE STRUCTURES TO BE CLEANED	EACH	13	13								
*	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1								
O *	Z0030240 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4								
O *	Z0030340 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	7	7								
∞ *	Z0076600 TRAINEES	HOUR	5000	5000								
*	XX001987 LINE STOPS 4'	EACH	4								4	
*	XX002957 REMOVE AND RE-ERECT EXISTING SIGN	EACH	10	10								
*	XX003516 CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	5								5	
*	XX003517 CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 6"	EACH	3								3	
*	XX003518 CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 4"	EACH	1								1	
*	XX003519 DUCTILE IRON WATER MAIN FITTINGS - 12" X 6" TEE	EACH	7								7	

- ▲ Non-Participating
- * SPECIAL PROVISION
- O SPECIALITY ITEM
- ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
- COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008
DRAWN BY JMH
CHECKED BY JCM