

FAP SITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE	J000-2A	TRAFFIC SIGNALS IL 59 @ FRASER 80% FED 10% STATE 10% VILLAGE	Y031-1F	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	Y031-1F	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE	Y031-1F	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	Y031-1F	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE	Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE	Y031-3D	WATER MAIN/ SANITARY SEWER 100% VILLAGE	Y060	SIDEWALK 50% STATE 50% VILLAGE	SFTY-B
* X0336855	PRECAST CONCRETE BOX CULVERT END SECTIONS 5' X 3'	EACH	2	2																	
* X0712400	TEMPORARY PAVEMENT	SQ YD	33,360	33,360																	
* X2111000	TOPSOIL EXCAVATION	CU YD	18,585	18,585																	
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	16	16																	
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	30	30																	
* X4023000	TEMPORARY ACCESS (ROAD)	EACH	14	14																	
* X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	3	3																	
* X4200500	HIGH EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	2,765	2,765																	
* X064500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (TEMPORARY)	FOOT	165	165																	
O * X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2	2																	
* X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	27	27																	
O * X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3			1		1		1											
O * X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	3			1		1		1											
O * X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62 5/125, MM12F SM12F	FOOT	7,628									7,628									
O * X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,037.5													2,037.5					
O * X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	873			290		313		270											
O * X8900015	TEMPORARY TRAFFIC SIGNAL INTERCONNECTION SYSTEM	L SUM	1											1							
* X0326000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (TEMPORARY)	FOOT	1,519	1,519																	
* X0326001	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12 (TEMPORARY)	FOOT	356	356																	
* X0326002	STORM SEWERS JACKED IN PLACE, 12" (SPECIAL)	FOOT	129	129																	
* X0323863	STORM SEWERS, (WATER MAIN REQUIREMENTS), TYPE 2, 12"	FOOT	611	519														92			
* X0323889	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 18"	FOOT	134	114														20			
* X0326003	TEMPORARY MANHOLE	EACH	1	1																	
* 56104000	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 10"	FOOT	22															22			

- * SPECIAL PROVISION
- O SPECIALITY ITEM
- OO CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
- COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE DRAWN BY JMH
DATE MARCH 18, 2008 CHECKED BY JCM