

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	34
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FAP 338 (IL RTE. 59)		

TEMPORARY PAVEMENT SCHEDULE				
FROM STATION	TO STATION	OFFSET (LT/RT/CL)	ROAD	X0712400 TEMPORARY PAVEMENT (SQ YD)
PRE-STAGE 1				
3193+25	3206+26	LT	IL 59	1,968
3205+82	3207+84	CL	IL 59	310
3213+60	3213+99	CL	IL 59	76
3213+60	3260+00	RT	IL 59	7,230
3257+00	3265+00	LT	IL 59	965
3262+99	3266+75	RT	IL 59	836
696+24	699+66	LT	FRASER RD.	302
3267+13	3285+41	RT	FEENEY DR./IL 59	2,974
3285+93	3293+30	RT	IL 59/RENWICK RD.	1,679
3293+61	3230+28	RT	RENWICKRD./IL 59	5,724
96+66	99+73	LT	RENWICK RD.	433
PRE-STAGE 1A				
3260+00	3263+00	RT	IL 59	622
PRE-STAGE 1B				
NO QUANTITY				
PRE-STAGE SUBTOTAL				23,120
STAGE 1				
3200+52	3206+11	RT	IL 59	600
696+24	699+69	RT	FRASER RD.	447
700+50	703+66	RT	FEENEY DR.	321
3269+70	3272+80	CL	IL 59	448
3287+50	3293+21	LT	IL 59	331
3287+50	3293+10	CL	IL 59	626
3295+75	3298+75	CL	IL 59	250
STAGE 1 SUBTOTAL				3,022
STAGE 1A				
3193+25	3198+50	CL	IL 59	525
3199+57	3199+88	CL	IL 59	61
3200+56	3206+26	CL	IL 59	588
3260+90	3266+24	LT	IL 59	575
3266+30	3267+00	CL	IL 59	101
3293+10	3293+54	CL	IL 59	49
3311+90	3319+83	LT	IL 59	854
3320+21	3323+96	LT	IL 59	304
STAGE 1A SUBTOTAL				3,057
STAGE 1B				
697+61	698+91	LT	FRASER RD.	127
3293+67	3296+28	LT	RENWICK RD./IL 59	313
STAGE 1B SUBTOTAL				440
STAGE 1C				
3267+00	3267+75	CL	IL 59	108
3293+54	3294+39	CL	IL 59	74
STAGE 1C SUBTOTAL				182

TEMPORARY PAVEMENT SCHEDULE CONTINUED				
FROM STATION	TO STATION	OFFSET (LT/RT/CL)	ROAD	X0712400 TEMPORARY PAVEMENT (SQ YD)
STAGE 2				
3220+10	3220+41	CL	IL 59	61
3220+93	3224+18	CL	IL 59	365
3247+76	3251+85	CL	IL 59	461
3256+35	3256+65	CL	IL 59	61
3260+50	3263+75	CL	IL 59	552
700+88	701+80	RT	FEENEY DR.	94
3267+56	3270+91	CL	IL 59	371
3279+88	3280+18	CL	IL 59	61
3285+00	3285+46	CL	IL 59	92
3286+06	3293+00	CL	IL 59	1,076
100+46	102+43	RT	RENWICK RD.	229
3294+74	3296+26	RT	IL 59	76
STAGE 2 SUBTOTAL				3,500
STAGE 2A				
NO QUANTITY				
STAGE 2A SUBTOTAL				0
STAGE 2B				
NO QUANTITY				
STAGE 2B SUBTOTAL				0
STAGE 2C				
3293+96	3294+74	RT	IL 59	38
STAGE 2C SUBTOTAL				38
STAGE 2D				
NO QUANTITY				
STAGE 2D SUBTOTAL				0
STAGE 3				
NO QUANTITY				
STAGE 3 SUBTOTAL				0
STAGE 3A				
NO QUANTITY				
STAGE 3A SUBTOTAL				0
STAGE 3B				
NO QUANTITY				
STAGE 3B SUBTOTAL				0
STAGE 4				
NO QUANTITY				
STAGE 4 SUBTOTAL				0
STAGE 4A				
NO QUANTITY				
STAGE 4A SUBTOTAL				0
PROJECT TOTAL				33,360

X6064500 COMBINATION CONCRETE CURB AND GUTTER (TEMPORARY) TYPE B-6.24			
STAGE	FROM STATION	TO STATION	LENGTH (FT)
Prestage 1	3207+20	3207+35	15
Prestage 1	3207+85	3208+00	15
Stage 1	3206+11	3206+26	15
Stage 1	3311+75	3311+90	15
Stage 1A	299+22	299+37	15
Stage 2	3225+31	3225+46	15
Stage 2	3247+76	3247+91	15
Stage 2	3252+99	3253+14	15
Stage 2	3256+65	3256+80	15
Stage 2	3273+00	3273+15	15
Stage 2	3280+18	3280+33	15
PROJECT TOTAL			165

COMBINATION CONCRETE CURB AND GUTTER (TEMPORARY) TYPE B-6.12			
STAGE	FROM STATION	TO STATION	LENGTH (FT)
Prestage 1	696+24	697+40	116
Prestage 1	3316+00	3326+25	1025
Prestage 1	3326+50	3328+00	150
Prestage 1	3328+00	3330+28	228
PROJECT TOTAL			1403

COMBINATION CONCRETE CURB AND GUTTER (TEMPORARY) TYPE B-9.12			
STAGE	FROM STATION	TO STATION	LENGTH (FT)
Stage 1B	697+40	699+67	229
Stage 1B	696+61	698+90	229
PROJECT TOTAL			229

ILLINOIS DEPARTMENT OF TRANSPORTATION
 DISTRICT NO. 1 SCHAUMBURG
 TEMPORARY PAVEMENT
 TEMPORARY CURB AND GUTTER
 SCHEDULE OF QUANTITIES

SCALE AS SHOWN
 DATE MARCH 18, 2008
 DRAWN BY JMH
 CHECKED BY JCM