

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL.	525	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

42000416 PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" X4200500 HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)			
FROM	TO	LT/RT	QUANTITY (SQ YD)
3193+25	3204+00	-	7610
3204+00	3206+26	LT	625
3204+00	3206+26	RT	602
3213+60	3218+00	LT	1173
3213+60	3218+00	RT	1173
3218+00	3232+00	-	8593
3232+00	3246+00	LT	3733
3232+00	3246+00	RT	4093
3246+00	3260+00	-	11447
3260+00	3274+00	-	11435
3274+00	3288+00	-	11581
3288+00	3302+00	-	10799
3302+00	3316+00	-	10041
3316+00	3327+30	-	8961
SUBTOTAL			91868
X4200500 HIGH-EARLY-STRENGTH PCC PAVEMENT 9 3/4" (JOINTED) (3% OF SUBTOTAL)			2756
42000416 PCC PAVEMENT, 9 3/4 INCH (JOINTED)			89112

Z0001050 AGGREGATE SUBGRADE, 12 INCH			
FROM	TO	LT/RT	QUANTITY (SQ YD)
3193+25	3204+00	-	8949
3204+00	3206+26	LT	751
3204+00	3206+26	RT	727
3213+60	3218+00	LT	1418
3213+60	3218+00	RT	1418
3218+00	3232+00	-	10134
3232+00	3246+00	-	9400
3246+00	3260+00	-	12459
3260+00	3274+00	-	13082
3274+00	3288+00	-	12706
3288+00	3302+00	-	14626
3302+00	3316+00	-	10861
3316+00	3327+30	-	8093
TOTAL			104624

GUARDRAIL SCHEDULE

STATION FROM	STATION TO	OFFSET (LT/RT)	63301210	63302000	X6330103
			REMOVE AND RE-ERECT SPBGR, TYPE A (FOOT)	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	REMOVE AND RE-ERECT TRAFFIC BARR TERM, TY 1 SPECIAL, TANGENT (EACH)
3205+10		RT			1
3205+77		RT		1	
3205+10	3206+70	RT	160		
3213+60	3215+10	LT	150		
3215+05		LT			1
TOTAL			310	1	2

35300400 PORTLAND CEMENT CONCRETE BASE COURSE, 9"				
Road	FROM	TO	LT/RT	AREA (SQ YD)
IL Route 59	3327+30	3328+58	LT	57
IL Route 59	3327+30	3330+16	RT	227
Renwick Road	96+10	98+55	RT	214
Renwick Road	102+42	104+00	LT	126
PROJECT TOTAL				624

AGGREGATE SHOULDERS SCHEDULE

FROM STATION	TO STATION	OFFSET (LT/RT/CL)	ROAD	LENGTH (FT)	QUANTITY (SF)	48101498 AGGREGATE SHOULDERS, TYPE B 4" (SQ YD)
SIDERoads						
300+75	301+50	LT	ROLF RD	71	142	16
300+77	301+50	RT	ROLF RD	69	138	15
598+60	599+18	LT	WEDGEWOOD CT	55	110	12
598+60	599+22	RT	WEDGEWOOD CT	59	118	13
200+60	201+10	LT	ROBERTS AVE	47	94	10
200+60	201+10	RT	ROBERTS AVE	47	94	10
ADJACENT TO TEMPORARY PAVEMENT						3738
TOTAL						3814

31101200 SUB-BASE GRANULAR MATERIAL, TYPE B 4"				
Road/Description	FROM	TO	LT/RT	AREA (SQ YD)
Under Temporary Pavement	-	-	-	33360
IL 59	3327+30	3328+58	LT	227
IL 59	3327+30	3330+16	RT	57
Renwick Road	96+23	98+55	RT	214
Renwick Road	102+43	104+08	LT	126
PROJECT TOTAL				33984

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

ROADWAY
SCHEDULE OF QUANTITIES

SCALE AS SHOWN
DATE MARCH 18, 2008
DRAWN BY JMH
CHECKED BY JCM