

P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2734	1821 RS-2	COOK	27	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62551

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31				
40600300	AGGREGATE (PRIME COAT)	TON	103	103				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	28	28				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	235	235				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	415	415				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2375	2375				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4340	4340				
42001300	PROTECTIVE COAT	SO YD	275	275				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	48850	48850				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1090	1090				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	14131	14131				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	550	550				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	31	31				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1035	1035				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	365	365				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	673	673				
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	21	21				
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	790	790				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	300	300				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9120	9120				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1390	1390				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27910	27910				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4510	4510				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	350	350				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1760	1760				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	515	515				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	17655	17655				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1390	1390				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27910	27910				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4510	4510				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350	350				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1760	1760				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	515	515				

NP=Non-Participating
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/2/2008 11:10:10 AM C:\WORK\40603800