

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A 80% FED. 20% STATE				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32	32				
40600300	AGGREGATE (PRIME COAT)	TON	159	159				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	24				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1097	1097				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1345	1345				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6870	6870				
42001300	PROTECTIVE COAT	SO YD	530	530				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	79400	79400				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3000	3000				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	4000	4000				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1985	1985				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	1191	1191				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	794	794				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	100	100				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9415	9415				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	292	292				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A 80% FED. 20% STATE				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2132	2132				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	450	450				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	430	430				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3140	3140				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	292	292				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34500	34500				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2132	2132				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	450	450				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	430	430				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	600	600				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	550	550				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2943	2943				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3435	3435				
X0301424	SILICONE JOINT SEALER	FOOT	260	260				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
@ 20070600	TRAINERS	HOUR	2000	2000				

NP = Non-Participating
 * SPECIALTY ITEM
 @ 1080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 US ROUTE 34
 BN RAILROAD TO HARLEM AVE. Rev.

Rev. 5-28-08

4/1/2008 8:48:13 AM C:\PROJECTS\10350\BNSF\CH04500