



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 4, 2008

SUBJECT: FAP Route 607
Project F-0607 (076)
Section 130 RS-3
Will County
Contract No. 62787
Item No. 66, June 13, 2008 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices to revise the Project Number.
2. Revised page 1 of the Special Provisions to revise the Project Number.
3. Please revise all other instances of ACNHF-0607 (076) in the Special Provisions to read F-0607 (076).
4. Revised the Cover Sheet to revise the Project Number.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62787

State Job # - C-91-256-04
 PPS NBR - 1-77031-0021
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 130RS-3

Project Number
 * F-0607/076/
 * REVISED : JUNE 3, 2008

Route
 FAP 607

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322256	TEMP INFO SIGNING	SQ FT	51.400				
X4067107	POL LB MM IL4.75 N50	TON	1,340.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0076600	TRAINEES	HOUR	1,000.000		0.800		800.000
20201006	GRADING & SHAP SHLDS	UNIT	188.000				
40600200	BIT MATLS PR CT	TON	13.000				
40600300	AGG PR CT	TON	64.000				
40600400	MIX CR JTS FLANGEWYS	TON	20.000				
40600895	CONSTRUC TEST STRIP	EACH	2.000				
40600982	HMA SURF REM BUTT JT	SQ YD	100.000				
40601005	HMA REPL OVER PATCH	TON	1,600.000				
40603335	HMA SC "D" N50	TON	2,670.000				
44000158	HMA SURF REM 2 1/4	SQ YD	31,737.000				
44002224	HMA RM OV PATCH 6	SQ YD	4,760.000				
44201753	CL D PATCH T2 9	SQ YD	2,856.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62787

State Job # - C-91-256-04
 PPS NBR - 1-77031-0021
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 130RS-3

Project Number
 * F-0607/076/
 * REVISED : JUNE 3, 2008

Route
 FAP 607

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201757	CL D PATCH T3 9	SQ YD	952.000				
44201759	CL D PATCH T4 9	SQ YD	952.000				
48102100	AGG WEDGE SHLD TYPE B	TON	1,687.000				
67000400	ENGR FIELD OFFICE A	CAL MO	2.000				
67100100	MOBILIZATION	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70300100	SHORT-TERM PAVT MKING	FOOT	10,180.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	196.000				
70300220	TEMP PVT MK LINE 4	FOOT	35,008.000				
70300240	TEMP PVT MK LINE 6	FOOT	360.000				
70300260	TEMP PVT MK LINE 12	FOOT	580.000				
70300280	TEMP PVT MK LINE 24	FOOT	30.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	196.000				
78000200	THPL PVT MK LINE 4	FOOT	35,008.000				
78000400	THPL PVT MK LINE 6	FOOT	360.000				

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2007, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of Route: FAP 607 (US 52 / Troy Road), Project **F-0607 (076)**, Section 130 RS-3, Will County, Contract 62787 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

Route: FAP 607 (US 52 / Troy Road)
Project **F-0607 (076)**
Section: 130 RS-3
County: Will
Contract No.: 62787

LOCATION OF PROJECT

This project begins on US 52 / Troy Road (FAP 607) approximately 69 feet West of Kendall County line and extends in a easterly direction through the Village of Shorewood in Will County to 340 feet east of the center line of River Road for a distance of 10,731 linear feet (2.03miles).

DESCRIPTION OF PROJECT

This is a resurfacing project and the work to be performed under this contract consist of pavement patching, hot-mix asphalt surface removal, resurfacing with 1-½" HMA surface course, Mixture D, ¾" and polymerized leveling binder (Machine Method), thermoplastic pavement markings and all incidental and collateral work necessary to complete the improvement as shown on the plans and as described herein.

MAINTENANCE OF ROADWAYS

Effective: September 30, 1985

Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

Revised 06/04/2008