

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A.I. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 94/90 | | COOK | 29 | 3 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

62993

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | URBAN | |
|---------------------|--|------------------|-----------------|-----------------|
| | | | QUANTITY | 100% STATE JOOO |
| 20200100 | EARTH EXCAVATION | CU YD | 280 | 280 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 59 | 59 |
| 21101645 | TOPSOIL FURNISH AND PLACE, 12" | SQ YD | 209 | 209 |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.16 | 0.16 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 14 | 14 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 14 | 14 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 14 | 14 |
| 25000800 | GROUND PREPARATION FOR SEEDING | ACRE | 0.16 | 0.16 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 484 | 484 |
| 42001300 | PROTECTIVE COAT | SQ YD | 58 | 58 |
| 44002020 | CONCRETE MEDIAN SURFACE REMOVAL | SQ FT | 345 | 345 |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 162 | 162 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 2.3 | 2.3 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 10.9 | 10.9 |
| 50300300 | PROTECTIVE COAT | SQ YD | 25 | 25 |
| 50300510 | RUSTICATION FINISH | SQ FT | 36 | 36 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 650 | 650 |
| 60618324 | CONCRETE MEDIAN SURFACE, 6" (SPECIAL) | SQ FT | 509 | 509 |
| 66400550 | CHAIN LINK FENCE, 4" (SPECIAL) | FOOT | 1,138 | 1,138 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 26 | 26 |
| X0323973 | SEDIMENT CONTROL, SILT FENCE | FOOT | 1,230 | 1,230 |
| X0323974 | SEDIMENT CONTROL, SILT FENCE MAINTENANCE | FOOT | 308 | 308 |
| X0324640 | FLUTED KNEE WALL | FOOT | 1,177 | 1,177 |
| X0350810 | BOLLARD REMOVAL | EACH | 3 | 3 |
| X6065740 | CONCRETE MEDIAN SURFACE, 5" (MODIFIED) | SQ FT | 12 | 12 |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 6 | 6 |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 |
| Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 1 | 1 |
| X0325091 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, ^{RESETTABLE}), TEST LEVEL 2 | EACH | 1 | 1 |
| Z0076600 | TRAINING | HOURL | | |
| 44008300 | CURB REMOVAL (PARTIAL) | FOOT | 92 | 92 |
| 63700155 | CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT | FOOT | 8 | 8 |
| X0324112 | BARRIER BASE | FOOT | 8 | 8 |

INDEX OF SHEETS

| SHEET | DESCRIPTION |
|--------|---|
| 1 | COVER SHEET |
| 2 | GENERAL NOTES AND PROJECT COMMITMENTS |
| 3 | SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS |
| 4 | EXISTING AND PROPOSED TYPICAL SECTIONS |
| 5-9 | ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS |
| 10-13 | EXISTING AND PROPOSED KNEE WALL PLANS |
| 14-17A | STRUCTURAL DETAILS |
| 18 | BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING |
| 19 | TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS |
| 20 | TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES |
| 21 | TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS |
| 22 | TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN |
| 23-29 | CROSS SECTIONS |

IDOT HIGHWAY STANDARDS

| SHEET | DESCRIPTION |
|-----------|---|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS |
| 001001-01 | AREAS OF REINFORCEMENT BARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 664001-01 | CHAIN LINK FENCE |
| 701601-05 | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN |
| 701701-05 | URBAN LANE CLOSURE, MULTILANE INTERSECTION |
| 701801-05 | LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph |
| 701901 | TRAFFIC CONTROL DEVICES |
| 720001 | SIGN PANEL MOUNTING DETAILS |
| 720006-01 | SIGN PANEL ERECTION DETAILS |
| 728001 | TELESCOPING STEEL SIGN SUPPORT |
| 731001 | BASE FOR TELESCOPING STEEL SIGN SUPPORT |

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NORTHBOUND KNEE WALLS (35TH ST TO 33RD ST)
SUMMARY OF QUANTITIES
INDEX OF SHEETS
HIGHWAY STANDARDS

SCALE: NONE
DATE: 02/08/08

DRAWN BY: JDC
CHECKED BY: DDM

Rev. 4-3-08

S00-1
3.05.02 PM
2/12/2008