

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	22	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62999

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	URBAN
				100% STATE
20200100	EARTH EXCAVATION	CU YD	132	132
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	132	132
25000210	SEEDING, CLASS 2A	ACRE	0.08	0.08
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8	8
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	8
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8	8
25000800	GROUND PREPARATION FOR SEEDING	ACRE	0.05	0.05
25100630	EROSION CONTROL BLANKET	SQ YD	364	364
42001300	PROTECTIVE COAT	SQ YD	27	27
44004250	PAVED SHOULDER REMOVAL	SQ YD	49	49
50300225	CONCRETE STRUCTURES	CU YD	2.5	2.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.9	1.9
50300300	PROTECTIVE COAT	SQ YD	71	71
50300510	RUSTICATION FINISH	SQ FT	35	35
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	400	400
60618324	CONCRETE MEDIAN SURFACE, 6" (SPECIAL)	SQ FT	188	188
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	580	580
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	624	624
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	156	156
X0324640	FLUTED KNEE WALL	FOOT	494	494
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	48	48
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1
Z0076600	TRAINEES	HOUR		
44002300	CURB REMOVAL (PARTIAL)	FOOT	59	59

INDEX OF SHEETS

SHEET	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES AND PROJECT COMMITMENTS
3	SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-9	ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS
10-11	EXISTING AND PROPOSED KNEE WALL PLANS
12-13A	STRUCTURAL DETAILS
14	BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING
15	TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS
16	TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
17	TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
18	TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN
19-22	CROSS SECTIONS

IDOT HIGHWAY STANDARDS

SHEET	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-01	CHAIN LINK FENCE
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-05	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph
701901	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
728001	TELESCOPING STEEL SIGN SUPPORT
731001	BASE FOR TELESCOPING STEEL SIGN SUPPORT

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
SOUTHBOUND KNEE WALLS (35TH ST TO 33RD ST)
SUMMARY OF QUANTITIES
INDEX OF SHEETS
HIGHWAY STANDARDS
SCALE: NONE
DATE: 02/08/08
DRAWN BY: JDC
CHECKED BY: DDM

SOQ-1

3-40-05 PM
2/12/2008

Rev