

F. A. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00146-00-TL	COOK	273	014
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 630C3

CODED PAY ITEM	PAY ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE Y031-1F VILLAGE OF CALUMET PARK							
			127th Street & Throop	127th Street & Ashland Avenue	127th Street & Marshfield	127th Street & Wood Street	Ashland Avenue & Vermont Avenue	127th Street & Bishop	127th Street & Paulina	
	INTERSECTION NUMBER →		34	35	36	37	38	39	40	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT								
44000600	SIDEWALK REMOVAL	SQ FT								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO								
67100100	MOBILIZATION	L SUM								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM								
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT								
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT								
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	1	1	1	1	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH								
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH								
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH								
85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH								
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	131	259	391	146	294	228	301	
87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT								
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1					1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT								
87900200	DRILL EXISTING HANDHOLE	EACH								
88500100	INDUCTIVE LOOP DETECTOR	EACH								
88700200	LIGHT DETECTOR	EACH	2	2	2	2	2	2	2	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	1	1	1	1	1	1	
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	1					1		
89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	1					1		
89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	1					1		
89502200	MODIFY EXISTING CONTROLLER	EACH								
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT								
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	45					45		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1		
XD301023	CONFIRMATION BEACON	EACH								
XD322131	EMERGENCY VEHICLE PREEMPTION PUSH BUTTON ASSEMBLY	EACH								
XB730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	131	259	391	146	294	228	301	
XB730350	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT								
XB780110	MODIFY EXISTING TYPE "D" FOUNDATION	EACH								
<del>XD007282</del>	MAGNETIC DETECTOR AMPLIFIER	EACH								
Z0076600	TRAINEES	HOUR	3.8	3.8	3.8	3.8	3.8	3.8	3.8	

\* PLANS MODIFIED BY  
ROBINSON ENGINEERING, LTD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**PROPOSED EMERGENCY VEHICLE PREEMPTION  
SUMMARY OF QUANTITIES  
VILLAGE OF CALUMET PARK**

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_

DATE 01/02/08

DRAWN BY JSZ  
CHECKED BY MRS

ROBINSON ENGINEERING, LTD.  
1700 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473  
708.321.4100 FAX 708.321.9809  
ILLINOIS DESIGN FIRM REGISTRATION NO. 14600152 07248 QUAN-01-02