

SCHEDULE OF QUANTITIES				
PAYITEM	UNIT	QUANTITY		
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	347		
LIGHT DETECTOR	EACH	Ž		
LIGHT DETECTOR AMPLIFIER	EACH	1		
ELECTRIC CABLE IN CONDUIT NO. 20 3/C. TWISTED, SHIELDED	FOOT	347		

## NOTE

\*1. THIS PLAN IS FOR THE PURPOSE OF INSTALLING EMERGENCY VEHICLE PREEMPTION EQUIPMENT AS SHOWN PER PLAN INDICATED IN THE SCHEDULE OF QUANTITIES. ALL OTHER EQUIPMENT SHOWN SHALL BE DISREGARDED.

2. FIRE STATION PUSH BUTTON SHALL CALL EVP SEQUENCE 2, PREMPTOR 3.

F. A. RTE.	SECTION 080014600TL		COUNTY	TOTAL SHEETS	SHEET NO
			COOK 2	273	259
STA.		T	O STA.		
FFO. ROAD DIST, NO. BLINOS		ILLINOIS	FEO. AID PRI	DARCIT	

## CONTRACT NO. 63003

## CABLE PLAN LEGEND

CABLE PLAN LEGEND					
EXISTING	PROPOSED				
0	G	8" TRAFFIC SIGNAL SECTION			
R	R	12" TRAFFIC SIGNAL SECTION			
w	w	12" PEDESTRIAN SIGNAL SECTION			
	<u>o</u>	12" PEDESTRIAN SIGNAL SECTION			
$\boxtimes$	$\blacksquare$	CONTROLLER CABINET			
-		SERVICE INSTALLATION			
IXI	Ť	TELEPHONE CONNECTION			
		MAGNETIC DETECTOR			
$\triangleright \!$	<b>&gt;</b>	EMERGENCY VEHICLE LIGHT DETECTOR			
D-0	<b>)-•</b>	CONFIRMATION BEACON			
•	•	PUSHBUTTON DETECTOR			
		VEHICLE DETECTOR, INDUCTION LOOP			
2	2	DENOTES NUMBER OF CONDUCTORS. ALL CABLE NO. 14 EXCEPT AS INDICATED. ALL LOOP DETECTOR CABLE TO BE SHIELDED.			
*P"	RY 64 6	SIGNAL FACE WITH BACKPLATE "P" INDICATES PROGRAMMED HEAD			
"E"		RAILROAD CONTROL CABINET			
"E"		ILLUMINATED SIGN, FIBOR OPTRIC "NO LEFT TURN"			
"E"	<b>R</b>	ILLUMINATED SIGN, FIBOR OPTRIC "NO RIGHT TURN"			
H/C   0	H/C	GROUND ROD AT HANDHOLE, DOUBLE HANDHOLE, OR CONTROLLER GROUND ROD AT POST OR MAST ARM POLE			
3	s  -	GROUND ROD AT ELECTRIC SERVICE INSTALLATION			

## VILLAGE OF THORNTON LOCATION NO. 125

ROBINSON ENGINEERING, LTD.
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 80473
(708) 331-8700 FAX.(708) 331-3205

07248-94F