

| | | | | |
|---------------------|----------------|----------|------------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2690 | 08-00065-00-SP | COOK | 12 | 3 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |
| CONTRACT NO. 63021 | | | | |

SUMMARY OF QUANTITIES

| LOCATION OF WORK | | | | STP | |
|-----------------------|--|--------|------------------|------------------------|--|
| | | | | WOLF ROAD | |
| | | | | 80% FEDERAL | |
| | | | | 20% LOCAL | |
| FUNDING SOURCE | | | | STP | |
| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | |
| ITEM # | ITEM | UNIT | TOTAL QUANTITIES | 1000-2A | |
| 31101100 | SUB-BASE GRANULAR MATERIAL, TYPE B | CU YD | 25 | 25 | |
| 35800200 | AGGREGATE BASE REPAIR | TON | 5 | 5 | |
| 40201000 | AGGREGATE FOR TEMPORARY ACCESS | TON | 10 | 10 | |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GAL | 15 | 15 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 1 | 1 | |
| 40603085 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 | TON | 7 | 7 | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 6 | 6 | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH | SQ FT | 315 | 315 | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 30 | 30 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 150 | 150 | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 315 | 315 | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 50 | 50 | |
| 60600605 | CONCRETE CURB, TYPE B | FOOT | 275 | 275 | |
| 67100100 | MOBILIZATION | L. SUM | 1 | 1 | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L. SUM | 1 | 1 | |
| 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L. SUM | 1 | 1 | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L. SUM | 1 | 1 | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L. SUM | 1 | 1 | |
| 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 6 | 6 | |
| 72900100 | METAL POST - TYPE A | FOOT | 24 | 24 | |
| *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 160 | 160 | |
| *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 120 | 120 | |
| *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 30 | 30 | |
| *78300400 | THERMOPLASTIC PAVEMENT MARKING REMOVAL | SQ FT | 210 | 210 | |
| Z0013798 | CONSTRUCTION LAYOUT | L. SUM | 1 | 1 | |
| XX005370 | PATTERN, COLOR, PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH <i>SPECIAL</i> | SQ FT | 882 | 882 | |

* INDICATES SPECIALTY ITEM

DATE: _____ BY: _____
 CHECKED BY: _____
 AUTOMATIC CHECKED: _____
 NO. _____

CHRISTOPHER B. BURKE ENGINEERING LTD. PLAN
 9575 West Higgins Road, Suite 800
 Rosemont, Illinois 60018
 (847) 823-0500



DATE: _____ BY: _____
 CHECKED BY: _____
 AUTOMATIC CHECKED: _____
 NO. _____

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---|
| NAME | DATE | |
| | | SUMMARY OF QUANTITIES CITY OF NORTHLAKE WOLF ROAD SCALE: _____ DRAWN BY: EDT DATE _____ CHECKED BY: AMP |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |