

F. A. U. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3500	06-00031-00-LS	COOK	5	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT # 63025

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. TYPICAL CROSS SECTIONS
5. SCENIC BEAUTIFICATION PLAN SHEET

HIGHWAY STANDARDS

606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701001-01	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 4.5m(15') AWAY
701006-02	OFF-RD OPERATIONS, 2L, 2W, 4.5m(15') TO 600mm(24") FROM PAVEMENT EDGE
701011-01	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901	TRAFFIC CONTROL DEVICES

GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
2. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
3. ITEMS OF WORK LISTED IN THE SUMMARY OF QUANTITIES WHICH ARE NOT SPECIFICALLY INDICATED IN THE PLANS SHALL BE PERFORMED AT LOCATIONS AS DIRECTED BY THE ENGINEER.

4. THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC., SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE VARIOUS ITEMS.

5. WHEN, IN THE CONSTRUCTION OPERATION, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SO THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH DAY BY THE CONTRACTOR AT HIS EXPENSE.

6. WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY OUTLETS AND CONNECTIONS FOR ALL PRIVATE OR PUBLIC DRAINS, SEWERS OR CATCH BASINS. HE SHALL PROVIDE FACILITIES TO TAKE ALL STORM WATER WHICH WILL BE RECEIVED BY THESE DRAINS AND SEWERS AND DISCHARGE SAME. HE SHALL PROVIDE AND MAINTAIN AN EFFICIENT PUMPING PLANT, IF NECESSARY, AND A TEMPORARY OUTLET, AND BE PREPARED AT ALL TIMES TO DISPOSE OF THE WATER RECEIVED FROM THESE TEMPORARY SEWER CONNECTIONS UNTIL SUCH TIME AS THE PERMANENT CONNECTIONS WITH SEWERS ARE BUILT AND IN SERVICE. THIS WORK WILL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

7. UTILITY CONFLICTS ARE NOT ANTICIPATED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LOCATIONS OF UNDERGROUND UTILITIES BEFORE STARTING CONSTRUCTION OPERATIONS. ANY NECESSARY ADJUSTMENT OF PUBLIC UTILITIES WITHIN THE LIMITS OF THIS IMPROVEMENT SHALL BE DONE BY THEIR RESPECTIVE OWNERS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED DUE TO DELAYS OR INCONVENIENCE CAUSED BY THESE ADJUSTMENTS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

8. ACCESS TO EXISTING BUSINESSES SHALL BE MAINTAINED THROUGHOUT THE LIFE OF THE CONTRACT. THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

9. THE CONTRACTOR SHALL FURNISH, ERECT AND MAINTAIN SUCH BARRICADES, SIGNS AND LIGHTS AS ARE NECESSARY TO SAFEGUARD TRAFFIC AND PROTECT THE WORK IN ACCORDANCE WITH ARTICLE 107.14 OF THE STANDARD SPECIFICATIONS, AS SPECIFIED HEREIN, AND AS REQUIRED BY THE MUNICIPALITY. SUCH BARRICADES, SIGNS AND LIGHTS SHALL BE PROVIDED WHEREVER REQUIRED TO PREVENT ANY ACCIDENT OR HARM TO LIFE, LIMB, PROPERTY OR THE WORK IN CONSEQUENCE OF THE EXCAVATION, USE OR OCCUPANCY OF STREETS, ALLEYS, HIGHWAYS OR RIGHT-OF-WAY. OPERATION OF FLASHER LIGHTS SHALL INCLUDE THE FURNISHING OF ALL ELECTRICAL ENERGY REQUIRED. THE BARRICADES, SIGNS AND LIGHTS SHALL BE KEPT IN OPERATION AND MAINTAINED BY THE CONTRACTOR AS LONG AS THEY ARE NEEDED TO SAFEGUARD TRAFFIC AND PROTECT THE WORK AS DETERMINED BY THE MUNICIPALITY. COMPLIANCE WITH THE ABOVE REQUIREMENTS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**INDEX OF SHEETS, HIGHWAY STANDARDS,
AND GENERAL NOTES
SCENIC BEAUTIFICATION
AT STATE STREET
FROM YATES TO HOXIE AVENUE**

SCALE: VERT. _____ DRAWN BY JZ
HORIZ. NONE CHECKED BY DWS
DATE 12-14-07

ROBINSON ENGINEERING, LTD.
1700 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 381-6700 FAX (708) 381-6500
ILLINOIS DESIGN FIRM REGISTRATION NO. 184001258 08479-NOTE-01 - P01