

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HBR-2	WINNEBAGO	171	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

78001110	PAINT PAVEMENT MARKING - LINE 4"				OFFSET	REMARKS
FOOT	LOCATION					
<u>AFTER STAGE 1</u>						
IL 251						
123.8	230 + 38.9	TO 235 + 33.9		NB		
59.8	238 + 33.9	TO 239 + 93.9		NB	RAMP AD	
300.0	251 + 14.9	TO 254 + 91.0		NB	RAMP CB & AC	
264.2	254 + 09.7	TO 255 + 84.7		SB	RAMP DA	
68.0	267 + 49.4	TO 270 + 20.0		SB	N OF SANDY HOLLOW	
<u>AFTER STAGE 1A</u>						
IL 251						
123.8	235 + 05.0	TO 240 + 00.0		NB		
<u>AFTER STAGE 2 & 3</u>						
US 20						
234.5	992 + 26.4	TO 994 + 60.9		EB	WHITE - SKIPDASH	
469.0	992 + 26.4	TO 994 + 60.9		EB	YELLOW - EDGELINE	
469.0	992 + 26.4	TO 994 + 60.9		EB	WHITE - EDGELINE	
234.5	992 + 26.4	TO 994 + 60.9		WB	WHITE - SKIPDASH	
469.0	992 + 26.4	TO 994 + 60.9		WB	YELLOW - EDGELINE	
469.0	992 + 26.4	TO 994 + 60.9		WB	WHITE - EDGELINE	
3284.6	TOTAL					

78200520	BARRIER WALL MARKERS TYPE B				OFFSET	REMARKS
EACH	LOCATION					
<u>US 20</u>						
36	988 + 10.2	TO 996 + 82.4		WB	TEMPORARY BARRIER WALLS	
36	990 + 13.8	TO 998 + 76.2		EB	TEMPORARY BARRIER WALLS	
20	992 + 26.7	TO 994 + 60.9		WB	PARAPET WALLS	
20	992 + 26.7	TO 994 + 60.9		EB	PARAPET WALLS	
112	TOTAL					

78201000	TERMINAL MARKER - DIRECT APPLIED				OFFSET	REMARKS
EACH	LOCATION					
<u>US 20</u>						
1	988 + 34.6			LT	EB	
1	991 + 22.1			RT	EB	
1	995 + 65.5			LT	WB	
1	998 + 53.0			RT	WB	
4	TOTAL					

78001140	PAINT PAVEMENT MARKING - LINE 8"				OFFSET	REMARKS
FOOT	LOCATION					
<u>AFTER STAGE 1</u>						
225	RAMP AD					
200	RAMP CB					
266	RAMP DA					
691	TOTAL					

78100100	RAISED REFLECTIVE PAVEMENT MARKER				OFFSET	REMARKS
EACH	LOCATION					
10	990 + 03.9	TO 996 + 70.9		EB	5 SETS OF 2	
10	990 + 16.4	TO 996 + 83.3		WB	5 SETS OF 2	
20	TOTAL					

78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)				OFFSET	REMARKS
EACH	LOCATION					
6	992 + 26.7	TO 994 + 60.9		EB	3 SETS OF 2	
6	992 + 26.7	TO 994 + 60.9		WB	3 SETS OF 2	
12	TOTAL					

78200410	GUARDRAIL MARKERS TYPE A				OFFSET	REMARKS
EACH	LOCATION					
<u>US 20</u>						
5	988 + 34.6	TO 992 + 27.6		LT	EB	
4	991 + 09.6	TO 992 + 27.6		LT	WB	
4	991 + 22.1	TO 992 + 27.6		RT	EB	
4	994 + 60.0	TO 995 + 65.5		LT	WB	
5	994 + 60.0	TO 998 + 53.0		RT	WB	
4	994 + 60.0	TO 995 + 78.0		RT	EB	
26	TOTAL					

PLOT DATE = Fri, Nov 14, 09:21:48, 2008
 FILE NAME = c:\projects\64292\801111.dgn
 PLOT SCALE = 1/8" = 1' / IN.
 USER NAME = dmsidd