CONTRACT NO. 64292

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HBR-2	WINNEBAGO	171	34
STA. 245+00	TO STA.260+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

IL RTE 251 (TEMPORARY PAVEMENT)

STA 244+90.3 TO STA 245+09.8
CLASS D PATCHES, TYPE IV, 9"
STA 245+00
60' PIPE CULVERTS, CLASS A,
TYPE 1, 24" (TEMPORARY)

STA 245+55.9
MEDIAN SPECIAL
TEMPORARY PAVEMENT
STA 249+22.92

STA 252+91.20 (IL RTE 251)=
STA 993+43.82 (US RTE 20)

STA 252+54.2

HOT MIX ASPHALT SURFACE REMOVAL, 2 1/4"
STA 249+22.92 TO STA 256+65.34

STA 31+41.63
36' PIPE CULVERT
CLASS A, TYPE 1, 24"
(TEMPORARY)

STA 260+09.0
STA 260+02.8
STA 259+71.0
STA 259+28.2

STA 256+65.34

STA 246+47.2

STA 248+09.3
COMBINATION CONCRETE
CURB & GUTTER, TYPE M-4.06

COMBINATION CONCRETE CURB
& GUTTER, TYPE M-4.24

STA 254+46.2

TEMPORARY PAVEMENT

STA 259+79.4

STA 2518+58.51
SKEW 54°13'14.24"
64' PIPE CULVERT
CLASS A, TYPE 1, 24"
2 EACH PRECAST REINFORCED
CONCRETE FLARED END
SECTIONS 24"

STA 10+76.33
52' PIPE CULVERT
CLASS A, TYPE 1, 24"
(TEMPORARY)

STA 248+91.3 TO STA 249+08.8
CLASS D PATCHES, TYPE IV, 9"
STA 249+00
45' PIPE CULVERTS, CLASS A,
TYPE 1, 24" (TEMPORARY)

RAMP CA
RAMP BD
RAMP CB
RAMP DA
RAMP AC
RAMP DB
RAMP AD
TEMP RAMP BD
TEMP RAMP AC
SCRUB

0 50' 100'

PROFILE WAS CUT FROM INSIDE EDGE OF NB LANE

	245+00	246+00	247+00	248+00	249+00	250+00	251+00	252+00	253+00	254+00	255+00	256+00	257+00
	735.37	735.05	734.83	734.77	734.75	734.76	734.81	734.91	735.02	735.07	735.18	735.29	735.36
	735.39	735.44	735.48	735.53	735.52	735.49	735.50	735.41	735.27	735.05	734.84	734.51	

PROFILE WAS CUT FROM INSIDE EDGE OF SB LANE

	245+00	246+00	247+00	248+00	249+00	250+00	251+00	252+00	253+00	254+00	255+00	256+00	257+00
	733.77	733.53	733.39	733.37	733.40	733.44	733.57	733.69	733.86	734.00	734.15	734.30	734.43
	734.46	734.44	734.56	734.59	734.60	734.66	734.70	734.72	734.64	734.47	734.26	734.03	

EARTH EXC = 1008.8 CY
EMBANKMENT = 149.2 CY
WASTE = 607.4 CY

PLAN
SURVEYED
DRAWN
ALIGNMENT CHECKED
GRADES CHECKED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
DRAWN
GRADES CHECKED
STRUCTURE NOTATIONS CHKD
NOTE BOOK
NO.
BY
DATE

PLOT DATE = Fri Mar 14 09:41:43 2008
FILE NAME = c:\projects\64292\sht\32798pln2.dgn
PLOT SCALE = 49.9999 ' / IN.
USER NAME = dosadd

IL RTE 251 (TEMPORARY PAVEMENT)