

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 754 (IL 76)	101M	Boone	48	4
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64A45				

Commitments

The Contractor shall submit to the Engineer a description of location, elevation, and coordinates for each permanent survey marker. The Engineer shall submit this information to the Survey Crew.

Aggregate Base Course, Type B, is provided in the plan quantities and shall be used only as needed when directed by the Engineer.

Right-of-way markers will be erected with the back face of the marker on the right-of-way line unless the new right-of-way line has been surveyed and pinned, in which instance the right-of-way markers will be erected 300 mm (12 inches) inside the new right-of-way line.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Mediacom	Commonwealth Edison Co.
Verizon	NICOR Gas Co.
Insight Communications of Rockford	

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date + 135 days.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Tree planting layout shall be performed by the District Landscape Architect. The trees will be spaced at five foot intervals. The length of the planting shall be determined by the total number of trees. The width shall be five feet. This entire area shall be mulched with hardwood wood chips, four inches thick, with weed barrier fabric. If the trees are to be placed at random, then each tree shall receive a five foot diameter of hardwood wood chips, four inches thick, with weed barrier fabric.

- As discussed with the Studies & Plans Engineer and the Project Engineer, this project will use the following foreslope to minimize impacts:
* Left Station 12+75 to 12+90 – 1:3 foreslope
- The Eddington front yard property at 4884 Walnut Grove Drive has a septic field that is not to be disrupted. No project work, including equipment or material storage, driving vehicles and equipment shall take place beyond the construction limits in the Eddington property front yard from the east side of their entrance to the Lancaster entrance.
- The tree at Station 13+20 offset 50 ft. Lt. on the Lancaster property shall be saved.
- The Conkling front yard property's private entrance at 4893 Walnut Grove Drive has two decorative stone block pillars that are not to be disrupted throughout construction of their new private entrance. No project work, including equipment or material storage, driving vehicles and equipment shall take place beyond the construction limits in the Conkling property entrance.
- The Lancaster front yard property at 4896 Walnut Grove Drive has a septic field that is not to be disrupted. No project work, including equipment and material storage, driving vehicles or equipment shall take place beyond the construction limits in the Lancaster property.
- The tree at Station 11+60 Rt. that is within the temporary easement will not be disturbed by the Contractor.