

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY-YO07 80% FED. 20% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	310	310
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	270	270
20200100	EARTH EXCAVATION	CU YD	3166	3166
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	201	201
25000210	SEEDING, CLASS 2A	ACRE	1	1
25000310	SEEDING, CLASS 4	ACRE	1.25	1.25
25000750	MOWING	ACRE	1	1
25100115	MULCH, METHOD 2	ACRE	1.75	1.75
25100630	EROSION CONTROL BLANKET	SQ YD	1177	1177
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900
28000300	TEMPORARY DITCH CHECKS	EACH	24	24
28000400	PERIMETER EROSION BARRIER	FOOT	1502	1502
28000500	INLET AND PIPE PROTECTION	EACH	1	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	428	428
28200200	FILTER FABRIC	SQ YD	428	428
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	270	270
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	105	105
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133
40600990	<b>TEMPORARY RAMP</b>	<b>SQ YD</b>	<b>40</b>	<b>40</b>
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	105	105
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	157	157
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	360	360
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	240	240
50105200	REMOVE EXISTING CULVERTS	EACH	1	1
50800105	REINFORCEMENT BARS	POUND	40170	40170

\* SPECIALTY ITEM ● 100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY-YO07 80% FED. 20% STATE
50800515	BAR SPLICERS	EACH	129	129
51500100	NAME PLATES	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	129	129
63500105	DELINEATORS	EACH	2	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	256	256
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2956	2956
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1024	1024
70400100	TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4128	4128
78300100	PAVEMENT MARKING REMOVAL	SQ FT	688	688
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	45	45
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	836	836
Z0005400	BREAKER-RUN CRUSHED STONE	TON	244	244
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0014800	CULVERT TO BE CLEANED	FOOT	50	50
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

\* SPECIALTY ITEM ● 100% STATE