

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION		
8"	923+95	94 RT	
8"	923+91	94 RT	
8"	923+47	83 RT	
8"	923+45	84 RT	
8"	923+39	94 RT	
8"	923+10	99 RT	
8"	923+06	105 RT	
8"	923+04	124 RT	
8"	922+78	115 RT	
8"	922+99	105 RT	
8"	923+00	90 RT	
8"	923+17	131 RT	
8"	923+35	103 RT	
8"	923+37	97 RT	
8"	923+39	94 RT	
10"	924+01	95 RT	
10"	923+96	95 RT	
10"	923+85	103 RT	
10"	923+37	97 RT	
10"	923+28	94 RT	
10"	923+00	131 RT	
12"	926+50	90 LT	
12"	923+75	92 RT	
12"	924+22	79 RT	
12"	923+11	100 RT	
12"	923+08	130 RT	
14"	924+01	100 RT	
14"	923+87	89 RT	
14"	922+68	125 RT	
14"	922+90	180 RT	
14"	923+46	92 RT	
310 TOTAL			

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION		
16"	926+42	70 LT	
16"	926+39	69 LT	
16"	926+42	86 LT	
16"	926+39	83 LT	
16"	927+56	96 LT	
16"	927+59	95 LT	
16"	923+09	109 RT	
16"	922+89	95 RT	
16"	923+49	113 RT	
18"	924+36	87 RT	
18"	924+11	91 RT	
18"	923+32	121 RT	
36"	926+34	60 LT	
36"	926+39	57 LT	
270 TOTAL			

20200100 EARTH EXCAVATION

STA. 922 + 25 TO STA. 929+25			
EARTH EX CUT (CY)	EARTH EX ADJ. SHRINK 25%	FILL (CY)	EARTH WORK BALANCE WASTE (CY)
3166	2375	464	1911

25000210 SEEDING, CLASS 2A

ACRE	LOCATION		
0.4	STA. 922 + 25 TO STA. 929 + 25	LT	
0.6	STA. 922 + 25 TO STA. 929 + 25	RT	
1 TOTAL			

25000310 SEEDING, CLASS 4

ACRE	LOCATION		
0.5	STA. 922 + 25 TO STA. 929 + 25	LT	
0.75	STA. 922 + 25 TO STA. 929 + 25	RT	
1.25 TOTAL			

25000750 MOWING

ACRE	LOCATION		
0.4	STA. 922 + 25 TO STA. 929 + 25	LT	
0.6	STA. 922 + 25 TO STA. 929 + 25	RT	
1 TOTAL			

25100115 MULCH, METHOD 2

ACRE	LOCATION		
1	STA. 922 + 25 TO STA. 929 + 25	LT	
0.75	STA. 922 + 25 TO STA. 929 + 25	RT	
1.75 TOTAL			

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION		
564	STA. 922 + 25 TO STA. 929 + 25	LT	
613	STA. 922 + 25 TO STA. 929 + 25	RT	
1177 TOTAL			

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION		
900	STA. 922 + 25 TO STA. 929 + 25	100 LB/ACRE	
900 TOTAL			

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION		
1	STA. 922 + 37	RT	
1	STA. 922 + 60	LT	
1	STA. 922 + 87	RT	
1	STA. 923 + 10	LT	
1	STA. 923 + 37	RT	
1	STA. 923 + 60	LT	
1	STA. 924 + 10	LT	
1	STA. 924 + 33	RT	
1	STA. 924 + 83	RT	
1	STA. 925 + 33	RT	
1	STA. 925 + 59	LT	
1	STA. 925 + 83	RT	
1	STA. 926 + 09	LT	
1	STA. 926 + 33	RT	
1	STA. 926 + 59	LT	
1	STA. 926 + 83	RT	
1	STA. 927 + 18	LT	
1	STA. 927 + 33	RT	
1	STA. 927 + 68	LT	
1	STA. 927 + 83	RT	
1	STA. 928 + 14	LT	
1	STA. 928 + 33	RT	
1	STA. 928 + 61	LT	
1	STA. 928 + 83	RT	
24 TOTAL			

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		
719	STA. 922 + 25 TO STA. 929 + 25	RT	
783	STA. 922 + 25 TO STA. 929 + 25	LT	
1502 TOTAL			

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION		
1	STA. 928 + 47	RT	
1 TOTAL			

28100107 STONE RIPRAP, CLASS A4

SQ YD	LOCATION		
350	STA. 923 + 95	RT (35'X90')	
78	STA. 924 + 80	LT (35'X20')	
428 TOTAL			

28200200 FILTER FABRIC

SQ YD	LOCATION		
350	STA. 923 + 95	RT	
78	STA. 924 + 80	LT	
428 TOTAL			

35101800 AGGREGATE BASE COURSE, TYPE B 6"

SQ YD	LOCATION		
160	STA. 923 + 94 TO STA. 924 + 74	RT, LT	
110	STA. 926 + 02 TO STA. 926 + 57	RT, LT	
270 TOTAL			

40600635 LEVELING BINDER (MACHINE METHOD), N70

TON	LOCATION		
105	STA. 922 + 25 TO STA. 929 + 25		
105 TOTAL			

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION		
66.5	STA. 922 + 25 TO STA. 922 + 50		
66.5	STA. 929 + 00 TO STA. 929 + 25		
133 TOTAL			

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION		
105	STA. 922 + 25 TO STA. 929 + 25	SHOULDERS LT, RT	
105 TOTAL			

40603340 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70

TON	LOCATION		
157	STA. 922 + 25 TO STA. 929 + 25		
157 TOTAL			

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

SQ YD	LOCATION		
213	STA. 923 + 94 TO STA. 924 + 74	(80'X24')	
147	STA. 926 + 02 TO STA. 926 + 57	(55'X24')	
360 TOTAL			

48203023 HOT-MIX ASPHALT SHOULDERS, 6-1/2"

SQ YD	LOCATION		
142	STA. 923 + 94 TO STA. 924 + 74	RT, LT	
98	STA. 926 + 02 TO STA. 926 + 57	RT, LT	
240 TOTAL			

50105200 REMOVE EXISTING CULVERTS

EACH	LOCATION		
1	STA. 926 + 27.88		
1 TOTAL			

63500105 DELINEATORS

EACH	LOCATION		
2	ONE AT EACH END OF PROPOSED CULVERT		
2 TOTAL			

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION		
1	STA. 922 + 00	52.63 LT	
1	STA. 923 + 75	130 RT	
1	STA. 922 + 47.3	134.05 RT	
1	STA. 924 + 00	90.0 LT	
1	STA. 924 + 50	86.15 RT	
1	STA. 926 + 00	90.0 LT	
1	STA. 926 + 50	110.0 LT	
1	STA. 927 + 50	110.0 LT	
1	STA. 929 + 00	51.69 LT	
9 TOTAL			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION		
1	MARKER PLACED NEAR THE PROPOSED STRUCTURE		
1 TOTAL			

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION		
144	STA. 922 + 25 TO STA. 929+25	CENTERLINE	
56	STA. 922 + 25 TO STA. 929+25	EOP RT	
56	STA. 922 + 25 TO STA. 929+25	EOP LT	
256 TOTAL			

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION		
873	STA. 921 + 11 TO STA. 929+84	STAGE 1, LT	
605	STA. 922 + 23 TO STA. 928+28	STAGE 1, RT	
605	STA. 922 + 23 TO STA. 928+28	STAGE 2, LT	
873	STA. 922 + 67 TO STA. 929+40	STAGE 2, RT	
2956 TOTAL			

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

FOOT	LOCATION		
12	STA. 920 + 51	STAGE 1,2	
12	STA. 930 + 00	STAGE 1,2	
24 TOTAL			

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION		
488	STA. 921 + 11 TO STA. 928+28	RT, LT STAGE 1	
536	STA. 920 + 51 TO STA. 930+00	RT, LT STAGE 2	
1024 TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION		
637.5	STA. 922 + 06.5 TO STA. 928 + 44	STAGE 1	
637.5 TOTAL			

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION		
637.5	STA. 922 + 06.5 TO STA. 928 + 44	STAGE 2	
637.5 TOTAL			

78001110 PAINT PAVEMENT MARKING-LINE 4"

FOOT	LOCATION		
1834	STA. 920 + 67 TO STA. 929+84	EOP	2 APPLICATIONS
1834	STA. 920 + 67 TO STA. 929+84	EOP	2 APPLICATIONS
460	STA. 920 + 67 TO STA. 929+84	CL SKIP DASH	2 APPLICATIONS
4128 TOTAL			

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION		
306	STA. 920 + 67 TO STA. 929+84	EOP	
306	STA. 920 + 67 TO STA. 929+84	EOP	
76	STA. 920 + 67 TO STA. 929+84	CENETRLINE	
688 TOTAL			

A2006714 TREE, QUERCUS MACROCARPA (BUR OAK), 1 3/4" CALIPER, BALLED AND BURLAPPED

EACH	LOCATION		
45	AS DIRECTED BY DISTRICT LANDSCAPE ARCHITECT		
45 TOTAL			

Z0014800 CULVERT TO BE CLEANED

FOOT	LOCATION		
50	STA. 924 + 50	25 RT TO 25 LT	30" ELLIPTICAL PIPE
50 TOTAL			

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
1	STA. 922 + 13	STAGE 1	
1	STA. 928 + 38	STAGE 1	
2 TOTAL			

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
1	STA. 922 + 13	STAGE 2	
1	STA. 928 + 38	STAGE 2	
2 TOTAL			