SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION		UNITS
STA 260+06	39' RT	12
STA 260+11	39' RT	12
STA 260+49	42' RT	8
STA 260+64	41' RT	13
STA 260+69	50' RT	7
STA 260+87	51' RT	9
STA 261+25	52' RT	7
STA 261+25	57' RT	7
STA 261+39	70' RT	11
STA 261+94	65' RT	7
STA 262+06	65' RT	7
STA 262+16	65' RT	13
STA 262+20	58' RT	12
STA 262+20	50' RT	12
STA 262+23	45' RT	6
STA 262+23	50' RT	11
STA 277+55	59' RT	8
STA 277+60	68' RT	12
STA 277+70	71' RT	12
STA 277+79	46' RT	7
STA 278+22	63' RT	6
STA 278+43	57' RT	9
STA 278+60	59' RT	6
STA 278+64	58' RT	6
STA 278+77	64' RT	7
STA 278+86	68' RT	12
STA 326+03	57' LT	7
STA 326+04	57' LT	8
STA 326+05	56' LT	8
STA 326+10	59' LT	9
STA 326+10	49' LT	8
STA 326+10	50' LT	8
STA 326+10	50' LT	8
STA 326+10	50' LT	8
STA 326+10	50' LT	8
STA 326+10	50' LT	8
STA 326+10	50' LT	8
	TOTAL	335

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION		UNITS
STA 277+00	32' RT	26
STA 278+22	55' RT	17
STA 325+41	56' RT	24
	TOTAL	67

25000210 SEEDING, CLASS 2A

LOCATION		ACRE
STA 27+50 TO 529+50	LT	1.19
STA 27+50 TO 529+50	RT	0.81
	TOTAL	2.00

25000310 SEEDING, CLASS 4

LOCATION		ACRE
STA 27+50 TO 529+50	LT	0.46
STA 27+50 TO 529+50	RT	0.54
	TOTAL	1.00

25000400 NITROGEN FERTILIZER NUTRIENT

LOCATION		POUND
STA 27+50 TO 529+50	LT	148.50
STA 27+50 TO 529+50	RT	121.50
	TOTAL	270

25000500 PHOSPHORUS FERTILIZER NUTRIENT

LOCATION		POUND
STA 27+50 TO 529+50	LT	148.50
STA 27+50 TO 529+50	RT	121.50
	TOTAL	270

25000600 POTASSIUM FERTILIZER NUTRIENT

LOCATION		POUND
STA 27+50 TO 529+50	LT	148.50
STA 27+50 TO 529+50	RT	121.50
	TOTAL	270

25000750 MOWING

LOCATION		ACRE
STA 27+50 TO 529+50	LT	1.65
STA 27+50 TO 529+50	RT	0.91
	TOTAL	3.00

25100115 MULCH, METHOD 2

LOCATION		ACRE
STA 27+50 TO 529+50	LT	1.65
STA 27+50 TO 529+50	RT	1.35
	TOTAL	3.00

25100630 EROSION CONTROL BLANKET

LOCATION		SQ YD
STA 27+00 TO 28+50	LT&RT	133.00
STA 28+74 TO 29+50	LT	34.00
STA. 259+50 TO 263+50	LT&RT	356.00
STA. 274+50 TO 281+50	LT	311.00
STA. 274+50 TO 277+43	RT	130.00
STA. 317+50 TO 329+00	LT	511.00
STA. 527+00 TO 529+50	RT	111.00
STA 527+50 TO 530+00	LT	111.00
	TOTAL	1697.00

25100900 TURF REINFORCEMENT MAT

LOCATION		SQ YD
STA 28+64	RT	75
STA 261+52	LT	39
STA 277+15	LT	65
	TOTAL	179

28000250 TEMPORARY EROSION CONTROL SEEDING

LOCATION		POUND
STA 27+50 TO 529+50	LT & RT	1500.00
	TOTAL	1500.00

28000300 TEMPORARY DITCH CHECKS

LOCATION		EACH
STA 27+25	LT	1
STA 27+50	LT & RT	2
STA 27+75	LT	1
STA 28+00	LT & RT	2
STA 28+25	LT	1
STA 29+00	LT	1
STA 29+25	LT	1
STA 259+75	RT	1
STA 260+00	LT & RT	2
STA 260+25	RT	1
STA 260+50	LT & RT	2
STA 260+75	RT	1
STA 261+00	LT & RT	2
STA 261+25	RT	1
STA 261+75	RT	1
STA 262+00	LT & RT	2
STA 262+25	RT	1
STA 262+50	LT & RT	2
STA 262+75	RT	1
STA 263+00	LT & RT	2
STA 263+25	RT	1
STA 274+75	RT	1
STA 275+00	LT & RT	2
STA 275+25	RT	1
STA 275+50	LT & RT	2
STA 275+75	RT	1
STA 276+00	LT & RT	2
STA 276+25	RT	1
STA 276+50	LT & RT	2
STA 276+75	RT	1
STA 277+00	RT	1
STA 277+25	RT	1
STA 278+00	LT	1
STA 278+25	RT	1
STA 279+00	LT	1
STA 280+00	LT	1
STA 281+00	LT	1
STA 318+00	LT	1
STA 318+50	LT	1
STA 319+00	LT	1
STA 319+50	LT	1
STA 320+00	LT	1
STA 320+50	LT	1
STA 321+00	LT	1
STA 321+50	LT	1
STA 322+00	LT	1
STA 322+50	LT	1
STA 323+00	LT	1
STA 323+50	LT	1
STA 324+00	LT	1
STA 327+50	LT	1
STA 328+50	LT	1
STA 527+50	RT	1
STA 528+00	LT & RT	2
STA 529+00	LT & RT	2
STA 529+50	LT & RT	2
	TOTAL	71

28000400 PERIMETER EROSION BARRIER

LOCATION		FOOT
STA 259+50 TO 261+00	LT	150
	TOTAL	150

28000500 INLET AND PIPE PROTECTION

LOCATION		EACH
STA 28+64	RT	1
STA 261+52	LT	1
STA 277+15	LT	1
STA 325+50	LT	1
STA 326+87	LT	1
STA 329+00	RT	1
STA 528+47	RT	1
	TOTAL	7

28100107 STONE RIPRAP, CLASS A4

LOCATION		SQ YD
STA 28+64	LT	47
STA 261+52	RT	17
STA 277+15	RT	96
STA 528+47	LT	62
	TOTAL	222

28200200 FILTER FABRIC

LOCATION		SQ YD
STA 28+64	LT	47
STA 261+52	RT	17
STA 277+15	RT	96
STA 528+47	LT	62
	TOTAL	222

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

LOCATION		SQ YD
STA 28+34 TO 28+94		179
STA 261+11 TO 261+93		237
STA 276+63.69 TO 277+66.0		298
STA 328+28.24 TO 328+44.2		46
STA 528+13.50 TO 528+80.5		202
	TOTAL	962

45100100 CRACK ROUTING (PAVEMENT)

LOCATION		FOOT
DETOUR ROUTE / PER SPECIAL PROVISION		31962
	TOTAL	31962

45100200 CRACK FILLING

LOCATION		POUND
DETOUR ROUTE / PER SPECIAL PROVISION		12785
	TOTAL	12785

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

LOCATION		EACH
STA 28+64		1
	TOTAL	1

50100400 REMOVAL OF EXISTING STRUCTURES NO. 2

LOCATION		EACH
STA 261+52		1
	TOTAL	1

50100500 REMOVAL OF EXISTING STRUCTURES NO. 3

LOCATION		EACH
STA 277+15		1
	TOTAL	1

50100600 REMOVAL OF EXISTING STRUCTURES NO. 4

LOCATION		EACH
STA 528+47		1
	TOTAL	1

50104400 CONCRETE HEADWALL REMOVAL

LOCATION		EACH
STA 328+28.24	LT & RT	2
STA 276+90	LT	1
	TOTAL	3

51500100 NAME PLATES

LOCATION		EACH
STA 28+64		1
STA 261+52		1
STA 277+15		1
STA 528+47		1
	TOTAL	4

54001001 BOX CULVERT END SECTION, CULVERT NO. 1

LOCATION		EACH
STA 28+64	LT	2
	TOTAL	2

54001002 BOX CULVERT END SECTION, CULVERT NO. 2

LOCATION		EACH
STA 261+52	RT	1
	TOTAL	1

PLOT DATE = Tue Feb 26 10:25:59 2008
FILE NAME = c:\projects\b28107\b28107cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = cushmanbw