

SCHEDULE OF QUANTITIES

<p>20200100 EARTH EXCAVATION CU YD LOCATION 1625 313+57.10 TO 323+66.81 (UNDER PAVEMENT & SHLD) 1625 TOTAL</p> <p>25000115 SEEDING CLASS 1B ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>25100115 MULCH METHOD 2 ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>28000250 TEMPORARY EROSION CONTROL SEEDING POUND LOCATION 400 PROJECT LIMITS 400 TOTAL</p> <p>35100100 AGGREGATE BASE COURSE, TYPE A TON LOCATION 1300 313+57.10 TO 323+66.81 (&VARIOUS) 1300 TOTAL</p> <p>42000501 PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL</p> <p>44000100 PAVEMENT REMOVAL SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL</p> <p>44004250 PAVED SHOULDER REMOVAL SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 1350 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2025 TOTAL</p>	<p>44213200 SAWCUTS FOOT LOCATION 126 323+66.81 EB 50 313+57.10 EB 176 TOTAL</p> <p>48300500 PORTLAND CEMENT CONCRETE SHOULDERS 10" SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (6 FT) EB 1350 313+57.10 TO 323+66.81 RT (12FT) EB 2025 TOTAL</p> <p>67100100 MOBILIZATION L SUM LOCATION 1 I-74 / 280 EB 1 TOTAL</p> <p>78005110 EPOXY PAVEMENT MARKING - LINE 4" FOOT LOCATION 1010 313+57.10 TO 323+66.81 LT (YELLOW) EB 1010 313+57.10 TO 323+66.81 RT (WHITE) EB 2212 313+57.10 TO 319+59.10 (PAINTED MEDIAN, WHITE) EB 4232 TOTAL</p> <p>78005140 EPOXY PAVEMENT MARKING - LINE 8" FOOT LOCATION 38 I-74 / 280 EB (PAINTED MEDIAN) 38 TOTAL</p> <p>Z0013798 CONSTRUCTION LAYOUT L SUM LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>Z0017202 DOWEL BARS 1 1/2" EACH LOCATION 64 313+57.10 TO 323+66.81 64 TOTAL</p>
--	--

64
64

⚠ 6-2-08

FILE NAME = C:\Projects\p203008\03000shts.dgn	USER NAME = dhtcloro	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 74	SECTION 01-3WSM-1	COUNTY ROCK ISLAND	TOTAL SHEETS 5	SHEET NO. 5
PLOT SCALE = 20.0000' = 1" H.L.		CHECKED -	REVISED -	SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 64094		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT _____		
PLOT DATE = Wed Feb 27 14:33:13 2008		DATE -	REVISED -							