

SUMMARY OF QUANTITIES

I-74 EB

URBAN
J000

PAY CODE	ITEM	UNIT	100% State QUANTITY
20200100	EARTH EXCAVATION	CU YD	1625
25000115	SEEDING, CLASS 1B	ACRE	1
25100115	MULCH, METHOD 2	ACRE	1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1300
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2750
44000100	PAVEMENT REMOVAL	SQ YD	2750
44004250	PAVED SHOULDER REMOVAL	SQ YD	2025
44213200	SAW CUTS	FOOT	176
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	2025
67100100	MOBILIZATION	L SUM	1
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	4232
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	38
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017202	DOWEL BARS 1 1/2"	EACH	64

* SPECIALTY ITEM

▲ REVISED 6-2-08

FILE NAME = C:\Projects\p203008\083008shs.dgn	USER NAME = dxtlorsa	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 74	SECTION 181-3WSM-1	COUNTY BOCK ISLAND	TOTAL SHEETS 2	SHEET NO. 2		
PLOT SCALE = 20.0000' / IN.						SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 64094		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		
PLOT DATE = Wed Feb 27 14:33:30 2008						DATE - _____						

SCHEDULE OF QUANTITIES

<p>20200100 EARTH EXCAVATION CU YD LOCATION 1625 313+57.10 TO 323+66.81 (UNDER PAVEMENT & SHLD) 1625 TOTAL</p> <p>25000115 SEEDING CLASS 1B ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>25100115 MULCH METHOD 2 ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>28000250 TEMPORARY EROSION CONTROL SEEDING POUND LOCATION 400 PROJECT LIMITS 400 TOTAL</p> <p>35100100 AGGREGATE BASE COURSE, TYPE A TON LOCATION 1300 313+57.10 TO 323+66.81 (&VARIOUS) 1300 TOTAL</p> <p>42000501 PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL</p> <p>44000100 PAVEMENT REMOVAL SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL</p> <p>44004250 PAVED SHOULDER REMOVAL SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 1350 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2025 TOTAL</p>	<p>44213200 SAWCUTS FOOT LOCATION 126 323+66.81 EB 50 313+57.10 EB 176 TOTAL</p> <p>48300500 PORTLAND CEMENT CONCRETE SHOULDERS 10" SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (6 FT) EB 1350 313+57.10 TO 323+66.81 RT (12FT) EB 2025 TOTAL</p> <p>67100100 MOBILIZATION L SUM LOCATION 1 I-74 / 280 EB 1 TOTAL</p> <p>78005110 EPOXY PAVEMENT MARKING - LINE 4" FOOT LOCATION 1010 313+57.10 TO 323+66.81 LT (YELLOW) EB 1010 313+57.10 TO 323+66.81 RT (WHITE) EB 2212 313+57.10 TO 319+59.10 (PAINTED MEDIAN, WHITE) EB 4232 TOTAL</p> <p>78005140 EPOXY PAVEMENT MARKING - LINE 8" FOOT LOCATION 38 I-74 / 280 EB (PAINTED MEDIAN) 38 TOTAL</p> <p>Z0013798 CONSTRUCTION LAYOUT L SUM LOCATION 1 PROJECT LIMITS 1 TOTAL</p> <p>Z0017202 DOWEL BARS 1 1/2" EACH LOCATION 64 313+57.10 TO 323+66.81 64 TOTAL</p>
--	--

64
64

6-2-08

FILE NAME = C:\Projects\p203008\03000shts.dgn	USER NAME = dhtclora	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.T. RTE. 74	SECTION 01-3WSM-1	COUNTY ROCK ISLAND	TOTAL SHEETS 5	SHEET NO. 5
PLOT SCALE = 20.0000' = 1" HL		CHECKED -	REVISED -	SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 64094		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		
PLOT DATE = Wed Feb 27 14:33:13 2008		DATE -	REVISED -							