

GENERAL NOTES

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price for MOBILIZATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION.

Install a "TO ACTIVATE SIGNAL" sign for the traffic signal detector loops. The detail of this sign is included in the plans. This work will be included in the cost of TRAFFIC CONTROL AND PROTECTION STANDARD 701316.

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

The Contractor shall sandblast the top of the beams upon removal of the bridge deck. This work will be included in the cost of CONCRETE REMOVAL.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

- Mediacom - Moline
- Gallatin River Communications - Galesburg
- Commonwealth Edison Company - Rockford
- Verizon - Sycamore
- Jo-Carroll Energy - Elizabeth
- NICOR Gas Co. - Naperville
- Frontier/Citizens - Lanark
- Insight Communications - Rockford

INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities
3. General Notes
4. Traffic Control Plan SN 008-0028
5. -6. Traffic Control Plan SN 071-0069
7. -8. Traffic Control Plan SN 089-0060
9. Traffic Control and Protection for Ramps

Structure Number 008-0028

10. General Plan & Elevation
11. Existing Deck Plan & Cross Section
12. Existing Deck Plan & Cross Section
13. Joint Details
14. Joint Details
15. Preformed Joint Strip Seal
16. Bar Splicer Assembly Details

Structure Number 071-0069

17. General Plan & Elevation
18. Existing Deck Plan & Cross Section
19. Joint Details
20. Preformed Joint Strip Seal
21. Bar Splicer Assembly Details

Structure Number 089-0060

22. General Plan & Elevation
23. Existing Deck Plan and Cross Section
24. Joint Details
25. Preformed Joint Strip Seal
26. Bar Splicer Assembly Details

STANDARDS

- 701201-02 Lane Closure, 2L, 2W, Day Only, for Speeds > 45 MPH
- 701321-09 Lane Closure, 2L, 2W, Bridge Repair with Barrier
- 701400-02 Approach to Lane Closure, Freeway/Expressway
- 701401-04 Lane Closure, Freeway/Expressway
- 701901 Traffic Control Devices
- 704001-04 Temporary Concrete Barrier

* Various
** (106BR)M, (4B-2)M & 177-4B-3)M

FILE NAME =	USER NAME = lmkdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BR\CADD plans\Various Counties\Contract #64099 2008 expansion joints\0080028.dgn	DRAWN -	REVISED -	*					**	Various	26	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	ILLINOIS					CONTRACT NO. 64099				
PLOT DATE = Sat Mar 15 11:20:55 2008	DATE -	REVISED -	FED. ROAD DIST. NO.					ILLINOIS FED. AID PROJECT				