

MAINLINE												
STATIONS	HMA SURF REM	HMA SURF REM	MIX FOR CRKS, JTS FLANGE	LEV BIND (HM) N70	EXC & GRAD EXIST SHLD	HMA SHLDS 6"	BIT MAT PRIME COAT	AGG PR CT	LEV BIND (MM) N70	HMA SURFACE COURSE "D", N70	AGG WEDGE SHLD TY B	TEMP RAMP
	1 1/2"	BT JT										
	SQ YD	SQ YD	TON	TON	UNIT	SQ YD	GALLON	TON	TON	TON	TON	SQ YD
1103+30 - 1105+07BK	312	160	0.14	0.24	3.5	78.7	44.1	1.1	23.6	46.3	14.3	15.6
9+00AH - 16+16.5	1911		0.57	0.96	14.3	318.4	178.4	4.5	95.5	187.3	57.8	
16+16.5 - 16+56.5	125				0.8	17.8	11.4	0.3		12.0	3.2	
16+56.5 - 108+08	24404		7.32	12.20	183.0	4067.3	2277.7	56.9	1219.7	2391.6	737.9	15.6
108+08 - 108+30	STRUCTURE 047-0016											
108+30 - 335+73.2	60649		18.19	30.32	454.9	10108.0	5660.6	141.5	3031.2	5943.6	1,833.9	31.2
335+73.2 - 337+80.8	STRUCTURE 047-0060											
337+80.8 - 437+60	26451	160	7.98	13.31	199.6	4435.1	2483.7	62.1	1330.0	2607.9	804.7	31.2
437+60 - 442+40	RIDGE ROAD OMISSION											
442+40 - 488+52	12139	160	3.69	6.15	92.2	2049.8	1147.9	28.7	614.7	1205.3	371.9	31.2
TOTALS	125991	480	38	63	948	21075	11804	295	6315	12394	3824	125

PATCHING	
LOCATION	CLASS D PATCH 15 INCH
	SQ YD
BEGIN JOB TO ASHLEY RD	8 @ 8
ASHLEY RD TO CHURCH RD	6 @ 8
CHURCH RD TO BRISBIN RD	6 @ 8
BRISBIN RD TO GROVE RD	4 @ 8
GROVE RD TO O'BRIEN RD	6 @ 8
O'BRIEN RD TO MCKANNA RD	2 @ 8
MCKANNA RD TO JUGHANDLE RD	8 @ 8
JUGHANDLE RD TO ARBEITER RD	4 @ 8
ARBEITER RD TO RIDGE RD	6 @ 8
RIDGE RD TO END JOB	6 @ 8
TOTALS	448

SIDEROADS AND ENTRANCES						
STATION	NUMBER	BIT MATLS PR CT	AGG PR CT	INC HMA SURF	HMA SURF REMOVAL 1 1/2"	TEMP RAMP
		GALLON	TON	TON	SQ YD	SQ YD
COMMERCIAL ENTRANCES	4	19		29	180	
PRIVATE ENTRANCES	43	110		165	1376	
MAILBOX TURNOUTS	39	87		131	1092	
SIDEROADS	12	115	2.9	158	960	266
TOTALS		332	2.9	483	3608	266

PAVEMENT MARKING				
LOCATION	PAINT PAVT MK LINE 4"		PAINT PAVT MK LINE 6"	RAISED REFL PVT MARK EACH
	WHITE	YELLOW	YELLOW	
	FOOT	FOOT	FOOT	
1103+30 - 1105+07BK				
CENTERLINE			50	2
EDGELINES	354			
NO PASSING ZONES		177		
9+00AH - 488+52				
CENTERLINE			11870	594
EDGELINES	94944			
NO PASSING ZONES		2523		
TOTALS	95298	2700	11920	596