

PLAN

S.N. 032-0023

S.N. 032-0023

DECK PATCHING SURVEY

TOTAL DECK AREA = 930.7 SQ. YDS.

TOTAL ESTIMATED DECK SLAB REPAIR AREA = 185 SQ. YDS.



DATE OF SURVEY: 08/10/2007

NOTES

LENGTHS AND WIDTH OF REPAIR AREAS WERE MEASURED AS INDICATED ON THE PLAN DETAIL.

THE ENGINEER SHALL SOUND THE REPAIR AREAS AS INDICATED ON THE PLAN DETAILS TO DETERMINE EXACT LIMITS OF DECK SLAB REPAIR PRIOR TO THE CONTRACTOR BEGINNING DECK SLAB REPAIR OPERATIONS.

LEGEND

-  DECK SLAB REPAIR (PARTIAL)
-  DECK SLAB REPAIR (FULL DEPTH) TYPE II

BILL OF MATERIAL

ITEM	UNIT	TOTAL
DECK SLAB REPAIR (PARTIAL)	SQ YD	161
DECK SLAB REPAIR (FULL DEPTH) TYPE II	SQ YD	24

FILE NAME =	USER NAME = #USER#	DESIGNED - RON WOODSHANK	REVISED - 03/21/2008
#FILE#		DRAWN - RON WOODSHANK	REVISED - 03/21/2008
	PLOT SCALE = #SCALE#	CHECKED - ----	REVISED - ----
	PLOT DATE = #DATE#	DATE - -----	REVISED - ----

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DECK SLAB REPAIR

SCALE: SHEET NO. 1 OF 1 SHEETS STA. 571+00.67 TO STA. 573+01.17

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	68-111	GRUNDY	29	18
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 66728				