GENERAL NOTES

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE "JULIE" NUMBER IS 1-800-892-0123. A MINIMUM OF FORTY-EIGHT (48) HOURS ADVANCE NOTICE IS REQUIRED.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

PREPARED BY:

EXAMINED BY:

DISTRICT MATERIALS ENGINEER

DISTRICT OPERATIONS ENGINEER

	FILE NAME =	USER NAME = woodshankrl	DESIGNED -	RW	REVISED	
	c:\projects\cmain09\cm301\details.dgn		DRAWN -	RW	REVISED	_
		PLOT SCALE = 103.4029 '/ IN.	CHECKED -		REVISED	
1		PLOT DATE = Mer 07, 2008 - 12:46:29 PM	DATE -	~~~~~	REVISED	

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

	OFNIEDAL N	OTEO	F.A.I. RTE.	SECTION	COUNTY
	GENERAL N	OTES	180	(06-3,78-1)1-2	BUREAU/PUTN/
					CONTRA
SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. 50+15.58 TO STA. 80+98.75	FED. RO	DAD DIST. NO ILLINOIS	FED. AID PROJECT

F.A.I. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.		
180	(06-3,78-1)[-2	BUREAU/PUTNAM	12	2		
		CONTRACT NO. 66734				