SUMMARY OF QUANTITIES

DEKALB

CONSTRUCTION CODE TYPE: I000-2A — SFTY-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LASALLE COUNTY	DEKALB COUNTY	SN 019-2012 & SN 019-2015
20400800	FURNISHED EXCAVATION	CU YD	34		34	
25100630	EROSION CONTROL BLANKET	SQ YD	420		420	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	198	13	185	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12883	1170	11685	28
40600300	AGGREGATE (PRIME COAT)	TON	319	29	290	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	47	4	43	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	79	7	72	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6522	530	5978	14
40600895	CONSTRUCTING TEST STRIP	EACH	1		1	
40600990	TEMPORARY RAMP	SQ YD	307	14	293	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13246	1223	11994	29
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	361	7	354	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	160881	14623	145909	349
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	147434		147434	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2541	207	2330	4
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	13	2	11	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3	
67100100	MOBILIZATION	L SUM	1	0.1	0.9	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.1	0.9	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	23857	4119	19738	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	132222	14178	118044	
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	11940	1060	10880	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	52032	5599	46433	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	414		414	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	46		46	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	132048	14178	117870	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	11940	1060	10880	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	764	137	627	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	73		73	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1	
Z0055300	RUMBLE STRIP	EACH	3		3	

*SPECIALTY ITEMS

•LASALLE & DEKALB