

MAINLINE												
LOCATION	LENGTH	WIDTH	BIT MAT'L PR CT	AGG PRIME COAT	MIX CR, JT & FLGWY	LEV BIND (HM) N50	LEV BIND (MM) N50	HMA SURF CSE "C", N50	HMA SURF REM 1 1/2"	STRIP REFL CR CONT SYSTM A	AGG WEDGE SHLDRS TYPE B	TEMP RAMP
STA. TO STA.	FOOT	FOOT	GAL	TON	TON	TON	TON	TON	SQ YD	FOOT	TON	SQ YD
LASALLE COUNTY												
1195+78 - 1211+32.8 BK	1554.8	26	359	8.98	1.35	2.25	189	377	4492		74	14.44
0+00 AH - 0+37	37	26	9	0.21	0.03	0.05	4	9	107		2	
0+37 - 1+89	152	25	34	0.84	0.13	0.21		35	422			
1+89 - 2+55	66	23	13	0.34	0.05	0.08		14	169			
2+55 - 2+87	32	21.5	6	0.15	0.02	0.04		6	76			
2+87 - 3+87	100	19.5	17	0.43	0.07	0.11		18	217			
3+87 - 4+20	33	18	5	0.13	0.02	0.03		6	66			
4+20 - 5+20	100	19.5	17	0.43	0.07	0.11		18	217			
5+20 - 5+53	33	21.5	6	0.16	0.02	0.04		7	79			
5+53 - 6+20	67	23	14	0.34	0.05	0.09		14	171			
6+20 - 8+14	194	24	41	1.03	0.16	0.26		43	517			
8+14 - 35+94.36	2780.36	26	643	16.06	2.41	4.02	337	675	8032		132	
COUNTY SUBTOTAL			1165	29	4	7	530	1223	14565	0	207	14
DEKALB COUNTY												
35+94.36 - 167+62.2 BK	13167.84	26	3043	76.08	11.41	19.02	1598	3195	38040	39504	624	
167+58.4 AH - 271+00	10341.6	26	2390	59.75	8.96	14.94	1255	2510	29876	31025	490	
271+00 - 271+20	20	32	6	0.14	0.02	0.04	3	6	71	60	1	
271+20 - 271+90 SN 019-2012	70	32	20	0.50	0.07	0.12	10	21	249		3	
271+90 - 272+15	25	32	7	0.18	0.03	0.04	4	7	89	75	1	
272+15 - 300+00 BK	2785	26	644	16.09	2.41	4.02	338	676	8046	8355	132	
300+05.7 AH - 422+67	12261.3	26	2834	70.84	10.63	17.71	1488	2975	35422	36784	581	
422+67 - 424+55	188	32	53	1.34	0.20	0.33	28	56	668	564	9	
424+55 - 424+83 SN 019-2015	28	32	8	0.20	0.03	0.05	4	8	100		1	
424+83 - 427+80	297	32	84	2.11	0.32	0.53	44	89	1056	891	14	
427+80 - 505+66.1 BK	7786.1	26	1799	44.99	6.75	11.25	945	1889	22493	23358	369	
505+64.1 AH - 528+37	2272.9	26	525	13.13	1.97	3.28	276	552	6566	6819	108	14.44
528+37 - 546+17.9	PERMIT IMPROVEMENT - OMISSION											
546+17.9 - 546+96.4	78.5	35	24	0.61	0.09	0.15		26	305			28.88
546+96.4 - 547+06.4	RAILROAD OMISSION											
547+06.4 - 547+31.4	25	54	12	0.30	0.05	0.08		13	150			28.88
COUNTY SUBTOTAL			11450	286	43	72	5992	12023	143131	147434	2334	72
TOTALS			12616	315	47	79	6523	13246	157695	147434	2542	87

FILE NAME =
c:\projects\ed\1508\details.dgn

USER NAME = duncanbd
DESIGNED -
DRAWN -
PLOT SCALE = 50.0000' / IN.
CHECKED -
PLOT DATE = Mar 26, 2008 - 09:28:08 AM
DATE -

REVISIED -
REVISIED -
REVISIED -
REVISIED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

*LASALLE & DEKALB
F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
68 (30,31,31XRS-3) 30 5
CONTRACT NO. 66749
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT