

PAVEMENT MARKING

LOCATION STA TO STA	DESCRIPTION	LENGTH FOOT	PAINT PAVEMENT MARKING			THERMOPLASTIC			TEMP PAINT PAVT MARKING			SHORT TERM PVT MKG FOOT	WORK ZONE PAVT MKING REMOVAL SQ FT	RAISED REFLEC PAVT MKR EACH	RAISED REFL PAVT MKR REMOVAL EACH
			LINE 4"		LINE 6"	LINE 4"		LINE 24"	LINE 4"		LINE 6"				
			WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	YELLOW FOOT				
LASALLE COUNTY															
CENTERLINES															
1195+78 TO 1200+18	DASH	440			110						110	176	70	7	
1200+18 TO 1210+01	DASH LT, SOLID RT	983		983	250						983	393	485	13	
1210+01 TO 1211+32.8 BK	DOUBLE SOLID	131.8		264							264	53	92	3	
0+00 AHD TO 8+02	DOUBLE SOLID	802		1604							1604	321	561	11	
8+02 TO 18+31	SOLID LT, DASH RT	1029		1029	260						1029	412	507	14	
18+31 TO 35+94.36	DASH	1763.36			440						440	705	279	23	
EDGELINES															
1195+78 TO 1211+32.8 BK	SOLID LT & RT	1554.8	3110							3110		622	1088	20	
0+00 AHD TO 35+94.36	SOLID LT & RT	3594.36	7189							7189		1438	2516	46	
LASALLE SUB-TOTALS			10298	3880	1060	0	0	0	10298	3880	1060	4119	5599	137	0
DEKALB COUNTY															
CENTERLINES															
35+94.36 TO 103+30	DASH	6735.64			1680							2694	1065	85	
103+30 TO 109+70	DASH LT, SOLID RT	640		640	160						640	256	315	9	
109+70 TO 111+96	DOUBLE SOLID	226		452							452	90	158	3	
111+96 TO 119+82	SOLID LT, DASH RT	786		786	200						786	314	388	10	
119+82 TO 162+20	DASH	4238			1060							1695	671	53	
162+20 TO 167+62.2 BK	DASH LT, SOLID RT	542.2		542	140						542	217	269	7	
167+58.4 AHD TO 170+38	DASH LT, SOLID RT	279.6		280	70						280	112	138	3	
170+38 TO 171+84	DASH	146			40						40	58	25	2	
171+84 TO 179+14	SOLID LT, DASH RT	730		730	180						730	292	358	9	
179+14 TO 300+00 BK	DASH	12086			3020							4834	1913	151	
300+05.7 AHD TO 393+67	DASH	9361.3			2340							3745	1482	117	39
393+67 TO 402+87	DASH LT, SOLID RT	920		920	230						920	368	452	12	
402+87 TO 432+70	DOUBLE SOLID	2983		5966							5966	1193	2088	37	
432+70 TO 441+51	SOLID LT, DASH RT	881		881	220						881	352	433	11	
441+51 TO 442+58	DOUBLE SOLID	107		214							214	43	75	2	
442+58 TO 452+05	DASH LT, SOLID RT	947		947	240						947	379	467	13	
452+05 TO 452+30	DOUBLE SOLID	25		50							50	10	18	0	
452+30 TO 463+67	SOLID LT, DASH RT	1137		1137	280						1137	455	557	14	
463+67 TO 496+10	DASH	3243			810							1297	513	42	
496+10 TO 504+68	DASH LT, SOLID RT	858		858	210						858	343	420	12	
504+68 TO 505+66.1 BK	DOUBLE SOLID	98.1		196							196	39	69	2	2
505+64.1 AHD TO 528+37	DOUBLE SOLID	2272.9		4546							4546	909	1591	29	29
528+37 TO 546+17.9	PERMIT IMPROVEMENT - OMISSION														
546+17.9 TO 546+96.4	DOUBLE SOLID	78.5					157				157	31	55	2	2
546+96.4 TO 547+06.4	RAILROAD OMISSION														
547+06.4 TO 547+31.4	DOUBLE SOLID	25					50				50	10	18	1	1
EDGELINES															
35+94.36 TO 167+62.2 BK	SOLID LT & RT	13167.84	26336								26336		8779		
167+58.4 AHD TO 300+00BK	SOLID LT & RT	13241.6	26483								26483		8828		
300+05.7 AHD TO 505+66.1 BK	SOLID LT & RT	20560.4	41121								41121		13707		
505+64.1 AHD TO 528+37	SOLID LT & RT	2272.9	4546								4546		1515		
528+37 TO 546+17.9	PERMIT IMPROVEMENT - OMISSION														
546+17.9 TO 546+96.4	SOLID LT & RT	78.5					157		22		157		52		
546+96.4 TO 547+06.4	RAILROAD OMISSION														
547+06.4 TO 547+31.4	SOLID LT & RT	25					50		24		50		17		
SUYDAM RD (CH 11) LT	SOLID LT & RT	30	60												
SUYDAM RD (CH 11) RT	SOLID LT & RT	30	60												
CHICAGO RD LT	SOLID LT & RT	30	60												
CHICAGO RD RT	SOLID LT & RT	30	60												
DEKALB SUB-TOTALS			98725	19145	10880	207	207	46	98692	19352	10880	19738	46433	627	73
TOTALS			132048		11940		414	46	132222		11940	23858	52032	764	73

*LASALLE & DEKALB

FILE NAME = c:\projects\ed01500\de\ta1a.dgn	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 68	SECTION (30,31,31X)RS-3	COUNTY =	TOTAL SHEETS 30	SHEET NO. 7
PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 66749
PLOT DATE = Mar 21, 2008 - 01:38:15 PM	CHECKED -	REVISED -								
	DATE -	REVISED -								