

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE	
				PROJECT 1	PROJECT 2
				PPS# 0-00859-3008 J000	PPS# 0-00859-3009 J000
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SQ YD	697	283	414
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SQ YD	140	80	60
44201048	CLASS B PATCHES, TYPE IV, 16 INCH	SQ YD	1596	854	742
44213100	PAVEMENT FABRIC	SQ YD	4113	2095	2018
44213200	SAW CUTS	FOOT	7570	3660	3910
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	32	16	16
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1795	902	893
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	400	220	180
Z0017202	DOWEL BARS 1 1/2"	EACH	2208	1020	1188
Z0075310	TIE BARS 3/4"	EACH	583	319	264

*SPECIALTY ITEM

FILE NAME = c:\projects\cmain\09\cm308\details.dgn	USER NAME = woodshankr1	DESIGNED <i>RLW</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN <i>RLW</i>	REVISED -			80	D3 PAVEMENT PATCHING	BUREAU	13	3	
		PLOT SCALE = 1/8" = 103.4029' / IN.	CHECKED -								
		PLOT DATE = Mar 27, 2008 - 08:42:26 AM	DATE -					FED. ROAD DIST. NO.	ILLINOIS		CONTRACT NO. 66778
				SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.				