

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	44
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	160
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	18.8
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	5.3
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	487
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	59.4
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	162
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	290
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	319
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	60
78300100	PAVEMENT MARKING REMOVAL	SQ FT	136
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	487
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	81
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY
ITEM

FILE NAME = c:\projects\deck beam repl 00\an 027-0077.dgn

USER NAME = woodshankr1	DESIGNED - RLW	REVISED - ---
DRAWN - RLW	CHECKED - ---	REVISED - ---
PLOT SCALE = 1/8" = 1'-0"	DATE - ---	REVISED - ---
PLOT DATE = Mar 27, 2008 - 09:02:09 AM		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(115-BR)	FORD	11	3
CONTRACT NO. 66801				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				