

SUMMARY OF QUANTITIES			80% FED. 20% STATE
CODE NO.	ITEM	CONSTRUCTION CODE TYPE: I000-2A	
		UNIT	TOTAL QUANTITY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	326
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	74
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4458
40600300	AGGREGATE (PRIME COAT)	TON	89
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13
40600535	LEVELING BINDER (HAND METHOD), N70	TON	22
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2282
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	130
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4563
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	139
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	389
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	44473
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	16297
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1237
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	11589
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6519
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4'	FOOT	47979
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6'	FOOT	3260
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18166
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	47979
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	3260
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	208
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	208

* SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
or\proj\state\0366802\0366802-sht-cover.dgn		DRAWN -	REVISED -			557	12BRS-4	DEKALB	11	3	
		CHECKED -	REVISED -			CONTRACT NO. 66802					
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
		PLOT SCALE = 50.0000' / IN.									
		PLOT DATE = Mar 29, 2008 - 09:38:25 AM									