

SUMMARY OF QUANTITIES				80% FED. 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY I000	
20400800	FURNISHED EXCAVATION	CU YD	122		122
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5792		5792
40600300	AGGREGATE (PRIME COAT)	TON	160		160
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22		22
40600535	LEVELING BINDER (HAND METHOD), N70	TON	36		36
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2980		2980
40600990	TEMPORARY RAMP	SQ YD	99		99
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5990		5990
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	159		159
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	69227		69227
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	264		264
44213200	SAW CUTS	FOOT	1584		1584
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1838		1838
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	16		16
63200310	GUARDRAIL REMOVAL	FOOT	800		800
67100100	MOBILIZATION	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9504		9504
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	47520		47520
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5940		5940
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	785		785
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47520		47520
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5940		5940
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	297		297
* 78201000	TERMINAL MARKERS-DIRECT APPLIED	EACH	16		16
Z0017100	DOWEL BARS	EACH	330		330

* SPECIALTY ITEMS