

MAINLINE													
LOCATION	WIDTH	LENGTH	AREA	HMA SURF REM 1 1/2"	HMA LEVEL BIND (HM)	LEVEL BINDER (MM) N70	HMA SC MIX "D" N70	MIX CR JTS FLANGEWYS	BIT MATLS PR CT	AGG PR CT	HMA SURF REM BUTT JT.	TEMP RAMP	AGG SHLD TY B
STATION	FT	FT	SQ YD	SQ YD	TON	TON	TON	TON	GAL	TON	SQ YD	SQ YD	TON
0.00 TO 2.7	26'	14256.0	41184.0	41184.0	20.6	1729.7	3459.5	12.4	3294.7	82.4	116.0	8.0	1082.4
2.7 TO 2.9	29'	1056.0	3402.7	3402.7	1.7	128.1	285.8	1.0	272.2	6.8	116.0	8.0	80.2
2.9 TO 3.52	26'	3274.0	9458.2	9458.2	4.7	397.2	794.5	2.8	756.7	18.9	116.0	8.0	248.6
3.52 TO 3.57	34'	264.0	997.3	997.3	0.5	41.9	83.8	0.3	79.8	2.0	116.0	8.0	8.0
3.57 TO 4.50	26'	4910.0	14184.4	14184.4	7.1	595.7	1191.5	4.3	1134.8	28.4	116.0	8.0	372.8
TOTALS		23760.0	69226.7	69226.7	35.7	2979.5	5989.5	21.4	5704.3	142.6	464.0	41.2	1837.5

PAVEMENT MARKING							
LOCATION	THPL PVT	THPL MK LN	TEMP PVT	TEMP MK LN	RAISED REF	SHORT TERM	WORK ZONE
	4"	6"	4"	6"	MKR	MKR	MKR
	WHITE	YEL	WHITE	YEL			REM
	FT	FT	FT	FT	EACH	FT	SQ FT
	0.00 TO 4.5	47520.0	5940.0	47520.0	5940.0	297	9504
TOTALS	47520.0	5940.0	47520.0	5940.0	297.0	9504.0	785.0

SIDE ROAD & ENTRANCES								
LOCATION	MILE	RT/LT	INCIDENTAL HMA SURF	BIT MATLS PR CT	HMA SURF REM. BUTT JT.	TEMP. RAMP	FURN. EX*	AGG PR CT
			TON	GAL	SQ YD	SQ YD	CU YD	TON
PROJECT BEGINS @ CITY LIMITS	0.00							
P.E.	0.05	RT	2.00	1.00	13.00			0.30
P.E./MAILBOX TURNOUT	0.10	RT	3.00	2.00				0.40
P.E./MAILBOX TURNOUT	0.12	RT	3.00	2.00				0.40
P.E./MAILBOX TURNOUT	0.40	RT	3.00	2.00				0.40
P.E./MAILBOX TURNOUT	0.50	RT	3.00	2.00				0.40
P.E.	0.55	LT	2.00	1.00				0.30
P.E./MAILBOX TURNOUT	0.60	LT	3.00	2.00	13.00			0.30
LOVER'S LANE	0.61	RT	10.00	5.00		8.00	2.00	1.20
P.E.	0.70	RT	2.00	1.00				0.30
P.E./MAILBOX TURNOUT	0.73	RT	3.00	2.00				0.40
P.E.	0.80	LT	2.00	1.00				0.20
P.E./MAILBOX TURNOUT	1.00	RT	3.00	2.00				0.30
P.E./MAILBOX TURNOUT	1.20	RT	3.00	2.00				0.30
P.E./MAILBOX TURNOUT	1.30	LT	3.00	2.00	13.00			0.30
SIDEROAD	1.40	LT	10.00	5.00	80.00	8.00		1.20
P.E.	1.50	LT	2.00	1.00				0.20
P.E.	1.60	LT	2.00	1.00				0.20
1950 EAST RD	1.70	LT	10.00	5.00	80.00	8.00	2.00	1.20
P.E.	1.71	RT	2.00	1.00				0.20
P.E.	2.00	RT	2.00	1.00				0.20
P.E./MAILBOX TURNOUT	2.01	LT	3.00	2.00				0.30
P.E.	2.10	LT/RT	4.00	2.00				0.30
P.E./MAILBOX TURNOUT	2.20	LT	3.00	2.00				0.30
P.E.	2.30	RT	2.00	1.00				0.20
P.E.	2.30	RT	2.00	1.00				0.20
MAILBOX TURNOUT	2.31	RT	1.00	1.00				0.20
P.E./MAILBOX TURNOUT	2.38	LT/RT	3.00	2.00				0.30
P.E./MAILBOX TURNOUT	2.40	LT/RT	3.00	2.00				0.30
P.E./MAILBOX TURNOUT	2.41	LT	3.00	2.00	13.00			0.30
P.E./MAILBOX TURNOUT	2.50	LT	3.00	2.00	13.00			0.30
P.E./MAILBOX TURNOUT	2.70	LT	3.00	2.00	13.00			0.30
P.E.	3.10	RT	2.00	1.00				0.20
P.E.	3.10	LT	2.00	1.00				0.20
P.E./MAILBOX TURNOUT	3.20	LT	2.00	1.00				0.20
MAILBOX TURNOUT	3.36	LT	1.00	1.00				0.20
P.E.	3.40	RT	2.00	1.00				0.20
P.E./MAILBOX TURNOUT	3.45	LT	3.00	2.00				0.30
SIDEROAD	3.60	LT	10.00	5.00		8.00	2.00	1.00
P.E./MAILBOX TURNOUT	3.61	RT	3.00	2.00				0.30
P.E./MAILBOX TURNOUT	3.70	RT	3.00	2.00				0.30
SIDEROAD	3.85	LT/RT	20.00	10.00	160.00	16.00	4.00	2.00
P.E./MAILBOX TURNOUT	4.30	LT	3.00	2.00				0.30
TOTALS			158.62	88.00	398.00	48.00	12.00	17.41

GUARDRAIL SCHEDULE					
LOCATION	SIDE	GUARDRAIL REMOVAL	TERMINAL MARKER, DIRECT APPLIED	TBT TYPE 1 SPECIAL TANGENT	FURNISHED EXCAVATION*
MILE MARKER	LT/RT	FOOT	FOOT	FOOT	CU YD
2.81	LT/RT	100	2	2	10
2.91	LT/RT	100	2	2	10
3	LT/RT	200	4	4	20
3.45	LT/RT	200	4	4	50
4.35	LT/RT	100	2	2	10
4.6	LT/RT	100	2	2	10
TOTAL		800	16	16	110

BUILD EMBANKMENT BY TBT, T1 END SECTIONS ACCORDING TO STANDARD 630301. THIS AREA TO BE SEEDED FERTILIZED, AND MULCHED-THESE ITEMS NOT TO BE PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION.

CLASS B PATCHING 13"						
STA (LOG MILES)	CL B PATCH TY II		DOWEL BARS		SAW CUTS	
	SQ YD		EACH		FOOT	
	NBL	SBL	NBL	SBL	NBL	SBL
LM 0.00 IS 1.34 MILES SOUTH OF PARK STREET						
0.1		8		10		48
0.3	8		10		48	
0.7	8	8	10	10	48	48
1		8		10		48
1.1		8		10		48
1.5	8		10		48	
2	8	8	10	10	48	48
2.3	8	8	10	10	48	48
3	8	8	10	10	48	48
3.2	8	8	10	10	48	48
3.4	8	8	10	10	48	48
3.9	8	8	10	10	48	48
4	8	8	10	10	48	48
4.1	8	8	10	10	48	48
4.15	8	8	10	10	48	48
4.15	8	8	10	10	48	48
4.25	8	8	10	10	48	48
4.3	8	8	10	10	48	48
4.35	8	8	10	10	48	48
TOTAL	128	136	160	170	768	816
GRAND TOTAL		264		330		1584

*PLACE FURNISHED EX AROUND SIDERAOD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION