

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	222
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	804
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13.9
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	14.9
50102400	CONCRETE REMOVAL	CU YD	9.3
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	895
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.3
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	103.8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,420
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	328
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	380

CONTINUED NEXT PAGE