

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

RURAL  
100% STATE  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	90
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	294
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	22.8
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	38.3
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	982
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	147.4
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	246
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	294
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	294
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	636
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	150
78300100	PAVEMENT MARKING REMOVAL	SQ FT	285
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	982
X0323078	REMOVE AND RE-ERECT EXISTING BRIDGE RAIL	FOOT	140
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

\*SPECIALTY  
ITEM

FILE NAME = c:\projects\deck beam repl 08\an 053-0137.dgn	USER NAME = woodshankr1	DESIGNED - RLW	REVISED - ---
		DRAWN - RLW	REVISED - ---
		CHECKED - ---	REVISED - ---
		DATE - ---	REVISED - ---

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>	
SCALE: _____	SHEET NO. 1 OF 1 SHEETS
STA. _____	TO STA. _____

F.A.S. RTE. 370	SECTION (102BR)I	COUNTY LIVINGSTON	TOTAL SHEETS 13	SHEET NO. 3
CONTRACT NO. 66814				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				