

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

SFTY-2A

RURAL  
100% STATE  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	94
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	342
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	4.8
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	337.8
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	10,390
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	42.7
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	85
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RLW	REVISED - ---
c:\projects\deck beam repl 08\an 027-0005.dgn		DRAWN - RLW	REVISED - ---
PLOT SCALE = 1/8" = 103.4829' / IN.		CHECKED - ---	REVISED - ---
PLOT DATE = Mar 27, 2008 - 10:52:28 AM		DATE - ---	REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

## SUMMARY OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET NO. 1 OF 1 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(19-BR-1)I	FORD	15	3
CONTRACT NO. 66819				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				