

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		Knox Co. Fed 80-State20 X271-2A				
44213200	SAW CUTS	FOOT	673.6	673.6				
50102400	CONCRETE REMOVAL	CU YD	73.2	73.2				
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2	2				
50157300	PROTECTIVE SHIELD	SQ YD	1472	1472				
50200100	STRUCTURE EXCAVATION	CU YD	427.4	427.4				
50300100	FLOOR DRAINS	EACH	20	20				
50300225	CONCRETE STRUCTURES	CU YD	28.3	28.3				
50300255	CONCRETE SUPER STRUCTURE	CU YD	907.5	907.5				
50300260	BRIDGE DECK GROOVING	SQ YD	2517	2517				
50300300	PROTECTIVE COAT	SQ YD	3020	3020				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	9550	9550				
50500505	STUD SHEAR CONNECTORS	EACH	12,150	12,150				
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	36	36				
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1				
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1	1				
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1				
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1	1				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	196,010	196,010				

FILE NAME	USER NAME = lajnedm	DESIGNED -	REVISED -
S:\GEN\DRAW\STD&PLNS\Squad\68216	Person\general.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/19/2008	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	(21-HB-1)	KNOX	55	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 68216	