

SUMMARY OF QUANTITIES				ROADWAY FAS 1360 80% FEDERAL 20% STATE	STRUCTURE SN. 102-0081 80% FEDERAL 20% STATE
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A	X071-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	972	972	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	72		72
21101615	TOPSOIL FURNISH AND PLACE, 4"	SD YD	135	135	
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
28000400	PERIMETER EROSION BARRIER	FOOT	1319	1319	
28100207	STONE RIPRAP, CLASS A4	TON	677		677
28200200	FILTER FABRIC	SD YD	733		733
42001165	BRIDGE APPROACH PAVEMENT	SD YD	222	222	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SD YD	44	44	
44000100	PAVEMENT REMOVAL	SD YD	222	222	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104650	SLOPE WALL REMOVAL	SD YD	216.9		216.9
50200100	STRUCTURE EXCAVATION	CU YD	222.4		222.4
50300100	FLOOR DRAINS	EACH	18		18
50300225	CONCRETE STRUCTURES	CU YD	83.4		83.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	182.3		182.3
50300260	BRIDGE DECK GROOVING	SD YD	512.2		512.2
50300280	CONCRETE ENCASEMENT	CU YD	15.4		15.4
50300300	PROTECTIVE COAT	SD YD	675.1		675.1
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2610		2610
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	51650		51650
50800515	BAR SPLICERS	EACH	66		66
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1326		1326
51202305	DRIVING PILES	FOOT	1326		1326
51203600	TEST PILE STEEL HP12X53	EACH	2		2
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	48		48
59100100	GEOCOMPOSITE WALL DRAIN	SD YD	52		52
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	110		110
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	575	575	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	980	980	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE, 4"	FOOT	511	511	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	511	511	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
X0301245	SHOULDER REMOVAL	SD YD	522	522	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	297	297	
X0325570	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	14	14	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1

*SPECIALTY ITEM

EFK Moen, LLC
Civil Engineering Design

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - MK	REVISED -			1360	65 BR	WOODFORD	39	3	
		CHECKED - SD	REVISED -			CONTRACT NO. 68530					
		DATE - 3/12/08	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
						SCALE: N.T.S.					