

## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION





STANDARD CONSTRUCTION

STAGE CONSTRUCTION

DESIGNED CTW

CHECKED CDL

DRAWN DP

CHECKED CTW

SB-1

11-1-06

ROUTE NO. SECTION COLARTY JOINS SEET NO. 17

FAS 1360 65-BR WOODFORD 39 30 19 SHEETS

FED. RONG DIST. NO. 7 ILLINGUS FED. ADD PROJECT-

Contract # 68530

When cantilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except as modified below and in the details shown on this sheet.

The finishing machine rails shall be placed on the top flange of the exterior beams.

The beams or girders, supporting cantilèver forming brackets, shall be fied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.

CANTILEVER FORMING BRACKETS
FOR SUPERSTRUCTURES WITH
W27 BEAMS AND SMALLER
F.A.S. ROUTE 1360 SEC. 65-BR
IL ROUTE 251 OVER PANTHER CREEK
WOODFORD COUNTY
STATION 1116+87.00
STRUCTURE NO. 102-0081

EFK • Moen, LLC Civil Engineering Design