

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693		TAZEWELL	82	17
IL 9				
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
•13R-1(9)TS(12B)I-1				

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	5
TOTAL	5

RR PROTECTIVE LIABILITY INSURANCE	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1

ENGINEER'S FIELD LABORATORY	
LOCATION	CAL MO
JOBSITE	5
TOTAL	5

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SO FT
IL. 9 & SECOND ST	287
TOTAL	287

COMBINATION CONCRETE CURB & GUTTER REMOVAL	
LOCATION	FOOT
IL 9 (EB) RT. STA. 105+88 TO STA. 107+93.8	216
IL 9 (EB) LT. STA. 105+88 TO STA. 109+11	353
SECOND ST RT. STA. 10+47 TO STA. 11+73.59	126.59
IL 9 (WB) RT. STA. 105+83 TO STA. 109+03	348
IL 9 (WB) LT. STA. 105+83 TO STA. 108+32	249
SECOND ST RT. STA. 9+12 TO STA. 9+85	105
SECOND ST LT. STA. 8+74 TO STA. 9+85	125
IL 9 (WB) LT. STA. 109+75 TO STA. 111+20	152
IL 9 (WB) LT. STA. 111+68 TO STA. 112+08	48
IL 9 (WB) RT. STA. 110+35 TO STA. 112+20	185
SECOND ST LT. STA. 10+19 TO STA. 10+80	123.5
SECOND ST LT. STA. 10+80 TO STA. 12+35	220.5
IL 9 (EB) LT. STA. 110+19 TO STA. 110+36.22	17.22
IL 9 (EB) RT. STA. 109+53 TO STA. 110+36.22	83.22
SECOND ST LT. STA. 12+74 TO STA. 14+05.6	148
TOTAL	2,500

MOBILIZATION	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1

SHORT-TERM PAVEMENT MARKING	
LOCATION	FOOT
IL 9 (EB) STA. 105+88 TO STA. 113+21	372
IL 9 (WB) STA. 105+83 TO STA. 112+20	232
SECOND ST STA. 8+50 TO STA. 14+92.5	408
TOTAL	1,012

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1

TEMPORARY RAMP	
LOCATION	SO YD
IL 9 (EB)/MARGARET ST	
STA. 110+36.22	20
STA. 113+21	20
SECOND STREET	
STA. 8+20	17.22
STA. 8+50	17.22
STA. 14+05.6	20
STA. 14+92.5	20
TOTAL	115

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL MO
JOBSITE	8
TOTAL	8

TRAFFIC CONTROL AND PROTECTION		
LOCATION	STD 701422	STD 701601
	L SUM	EACH
JOBSITE	1	1
TOTAL	1	1

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DAY
JOBSITE	25
TOTAL	25

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLOT DATE : 2/26/2008  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : bcrankin