

REMOVAL & DISPOSAL OF UNSUITABLE MATERIALS	
Location	Cu Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	711.1
Lt. Sta. 585 + 00 - 588 + 00	266.7
Total	978

POROUS GRANULAR EMBANKMENT	
Location	Cu Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	355.6
Lt. Sta. 585 + 00 - 588 + 00	133.3
Total	489

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
Location	Sq Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	1066.7
Lt. Sta. 585 + 00 - 588 + 00	400
Total	1467

AGGREGATE BASE COURSE, TYPE A	
Location	Cu Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	355.6
Lt. Sta. 585 + 00 - 588 + 00	133.3
Total	489

CR PCC PAVEMENT 10"	
Location	Sq Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	1066.7
Lt. Sta. 585 + 00 - 588 + 00	400
Total	1467

PAVEMENT REINFORCEMENT 10"	
Location	Sq Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	1066.7
Lt. Sta. 585 + 00 - 588 + 00	400
Total	1467

PAVEMENT REMOVAL	
Location	Sq Yd
SBL	
Lt. Sta. 454 + 00 - 462 + 00	1066.7
Lt. Sta. 585 + 00 - 588 + 00	400
Total	1467

PCC SHOULDERS 10"	
Location	Sq Yd
SBL	
Lt. Sta. 585 + 00 - 588 + 00	333
Total	333

PCC SHOULDER REMOVAL	
Location	Sq Yd
SBL	
Lt. Sta. 585 + 00 - 588 + 00	333
Total	333

SHOULDER REMOVAL & REPACEMENT	
Location	Foot
SBL	
Lt. Sta. 458 + 00	10
Lt. Sta. 462 + 00	10
Total	20

(for PIPE UNDERDRAIN 4", SPECIAL)

PIPE UNDERDRAINS 4"	
Location	Foot
SBL	
Lt. Sta. 454 + 00 - 462 + 00	800
Lt. Sta. 585 + 00 - 588 + 00	300
Total	1100

PIPE UNDERDRAINS 4" (SPECIAL)	
Location	Foot
SBL	
Lt. Sta. 458 + 00	27
Lt. Sta. 462 + 00	27
Lt. Sta. 585 + 00	27
Total	81

CONCRETE HEADWALL FOR PIPE DRAINS	
Location	Each
SBL	
Lt. Sta. 458 + 00	1
Lt. Sta. 462 + 00	1
Lt. Sta. 585 + 00	1
Total	3