

SCHEDULE OF QUANTITIES

LOCATIONS STA. TO STA.	CONCRETE MEDIAN REMOVAL	CONCRETE MEDIAN	TRAFFIC CONTROL SURVEILLANCE
	FOOT	SQ YD	CAL DAY
55+25 TO 55+39	14	91	3
TOTAL	14	91	3

LOCATIONS STA. TO STA.	COMB. CONC C & G REM & REPLACEMENT
	FOOT
55+18 TO 55+25	15
TOTAL	15

LOCATIONS	CHANGEABLE MESSAGE SIGN
	CAL DAY
* I-74 EB	14
* I-74 WB	14
** I-74 EB DETOUR	
2 BOARDS @ 4 DAYS	8
** I-74 WB DETOUR	
2 BOARDS @ 4 DAYS	8
** PINECREST NORTH	3
** PINECREST SOUTH	3
TOTAL	50

LOCATIONS STA. TO STA.	PAVEMENT PATCHING TYPE III, 8 INCH	PAVEMENT REMOVAL
	SQ YD	SQ YD
MEDIAN 55+18 TO 55+39	26.1	26.1
SHOULDER AT RAMP B	17.8	
TOTAL	43.9	26.1

LOCATIONS STA. TO STA.	TC & PROT TEMPORARY DETOUR	TRAFFIC CONTROL & PROTECTION (SPECIAL)
	L. SUM	L. SUM
JOBSITE	1	1
TOTAL	1	1

LOCATIONS STA. TO STA.	MOBILIZATION	TC & PROT STANDARD 701406	TC & PROT STANDARD 701411	ENGINEER FIELD OFFICE TYPE A
	L. SUM	L. SUM	EACH	CAL MO
JOBSITE	1	1	2	3
TOTAL	1	1	2	3

* TO BE PLACED 14 DAYS PRIOR TO ANY LANE CLOSURES ON I-74
 ** TO BE PLACED PRIOR TO AND DURING I-74 CLOSURE FOR BEAM REMOVAL & REPLACEMENT

LOCATIONS STA. TO STA.	PAVEMENT MARKING TAPE, TYPE III	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	SQ FT
57+86 TO 61+69	385	128.3
TOTAL	385	128.3

LOCATIONS STA. TO STA.	SHORT TERM PAVEMENT MARKING
	FOOT
PINECREST @ EB RAMPS	248
PINECREST @ WB RAMPS	124
TOTAL	372

LOCATIONS STA. TO STA.	TEMPORARY CONCRETE BARRIER
	FOOT
58+59 TO 60+71.5	212.5
TOTAL	212.5

LOCATIONS STA. TO STA.	IMPACT ATTENUATOR TEMPORARY (NON- REDIRECTIVE) TEST LEVEL 3
	EACH
58+59	1
TOTAL	1

FILE NAME =	USER NAME = mcfadden.jk	DESIGNED -	REVISED -
ca:\projec ts\pinecrest.l\bridge\d468803-design.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/28/2008	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	D4 MCHD 2008	TAZEWELL	14	7
CONTRACT NO. 68803				
FED. ROAD DIST. NO. 4 I-74 FED. AID PROJECT				