


SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS 502 (LEVERETT ROAD)  
 STA. 70+91.83  
 TO  
 STA. 71+85.17  
 CHAMPAIGN COUNTY

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	SUPERSTRUCTURE REPLACEMENT	SUBSTRUCTURE REPAIR	TOTAL
					80% FEDERAL 20% STATE X081-2A
20200100	EARTH EXCAVATION	CU YD	35		35
20400800	FURNISHED EXCAVATION	CU YD	107		107
25000210	SEEDING, CLASS 2A	ACRE	0.5		0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50		50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45		45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45		45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45		45
25100630	EROSION CONTROL BLANKET	SQ YD	1646		1646
28000310	AGGREGATE DITCH CHECKS	EACH	6		6
28000400	PERIMETER EROSION BARRIER	FOOT	976		976
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	38		38
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	8		8
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	54		54
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	174		174
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD		36	36
50105220	PIPE CULVERT REMOVAL	FOOT	115		115
50300225	CONCRETE STRUCTURES	CU YD		36	36
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2875		2875
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND		3710	3710
50901050	STEEL RAILING, TYPE SM	FOOT	180		180
51500100	NAME PLATES	EACH	1		1
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	693		693
59000200	EPOXY CRACK INJECTION	FOOT		36	36
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375		375
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4		4
63200310	GUARDRAIL REMOVAL	FOOT	390		390
67100100	MOBILIZATION	L SUM	1		1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16		16
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6		6
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	344		344
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12		12
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	328		328
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT		427	427

\* SPECIALTY ITEMS

FILE NAME = c:\projects\050704\050704.dwg



1170 SOUTH HOUBOLT ROAD  
 JOLIET, ILLINOIS 60431  
 (815) 744-4200  
 PLOT SCALE =  
 PLOT DATE = 3/24/2008

DESIGNED - RRD	REVISED -
DRAWN - KAS	REVISED -
CHECKED - JAR	REVISED -
DATE - 3/14/08	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE. 502	SECTION 186BR1BR	COUNTY CHAMPAIGN	TOTAL SHEETS 30	SHEET NO. 3
CONTRACT NO. 70426				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				