

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULES OF QUANTITIES

48101200 AGGREGATE SHOULDERS, TYPE B

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	(TON)
EB 608+76.00		EB 610+00.00 (BK)	124.0	4	55.1	1.5	4.5
WB 608+90.00		WB 610+00.00 (BK)	110.0	4	48.9	1.5	4.0
EB 633+68.77 (AH)		EB 655+70.00	2201.2	4	978.3	1.5	79.5
WB 633+68.77 (AH)		WB 666+29.87	3261.1	4	1449.4	1.5	117.8
EB 655+70.00		EB 659+74.37	404.4	4	179.7	1.5	14.6
EB 655+70.00		EB 662+33.70	663.7	4	295.0	1.5	24.0
WB 666+29.87		WB 675+79.87	950.0	4	422.2	1.5	34.3
WB 666+29.87		WB 679+10.15	1280.3	4	569.0	1.5	46.2
EB 659+74.37		EB 662+33.70	259.3	4	115.3	1.5	9.4
WB 675+79.87		WB 679+10.15	330.3	4	146.8	1.5	11.9
EB 662+33.70		EB 694+54.78	3221.1	4	1431.6	1.5	116.3
WB 679+10.15		WB 711+31.23	3221.1	4	1431.6	1.5	116.3
WB 711+31.23		WB 717+94.93	663.7	4	295.0	1.5	24.0
EB 694+54.78		EB 697+85.06	330.3	4	146.8	1.5	11.9
EB 694+54.78		EB 707+35.06	1280.3	4	569.0	1.5	46.2
WB 711+31.23		WB 713+90.56	259.3	4	115.3	1.5	9.4
EB 697+85.06		EB 707+35.06	950.0	4	422.2	1.5	34.3
WB 713+90.56		WB 717+94.93	404.4	4	179.7	1.5	14.6
EB 707+35.06		EB 829+63.00	12227.9	4	5434.6	1.5	441.6
EB 829+63.00		EB 836+25.23	662.2	4	294.3	1.5	23.9
EB 829+63.00		EB 836+25.23	662.2	4	294.3	1.5	23.9
EB 836+25.23		EB 857+10.70	2085.5	4	926.9	1.5	75.3
EB 857+10.70		EB 864+93.00	782.3	4	347.7	1.5	28.2
EB 857+10.70		EB 864+93.00	782.3	4	347.7	1.5	28.2
EB 864+93.00		EB 909+40.50	4447.5	4	1976.7	1.5	160.6
WB 717+94.93		WB 824+85.00	10690.1	4	4751.1	1.5	386.0
WB 824+85.00		WB 835+74.53	1089.5	4	484.2	1.5	39.3
WB 824+85.00		WB 835+74.53	1089.5	4	484.2	1.5	39.3
WB 835+74.73		WB 856+24.80	2050.1	4	911.1	1.5	74.0
WB 856+24.80		WB 863+06.00	681.2	4	302.8	1.5	24.6
WB 856+24.80		WB 863+06.00	681.2	4	302.8	1.5	24.6
WB 863+06.00		WB 910+00.00	4694.0	4	2086.2	1.5	169.5

SUB-TOTAL = 2,258.4

INTERCHANGE RAMPS

RAMP A	WB 106+62.40	WB 121+84.37	1521.97	4	676.4	1.875	68.7
RAMP A	WB 106+63.40	WB 121+85.37	1521.97	4	676.4	1.875	68.7
RAMP B	WB 200+24.84	WB 208+45.36	820.52	4	364.7	1.875	37.0
RAMP B	WB 200+25.84	WB 208+46.36	820.52	4	364.7	1.875	37.0
RAMP C	EB 306+62.40	EB 330+55.90	2393.50	4	1063.8	1.875	108.0
RAMP C	EB 306+63.40	EB 330+56.90	2393.50	4	1063.8	1.875	108.0
RAMP D	EB 400+24.84	EB 412+06.53	1181.69	4	525.2	1.875	53.3
RAMP D	EB 400+25.84	EB 412+07.53	1181.69	4	525.2	1.875	53.3

SUB-TOTAL = 534.2

CROSSOVERS

699+35.00	-	60.00	2	13.3	1.875	1.4
788+62.00	-	60.00	2	13.3	1.875	1.4

SUB-TOTAL = 2.7

TOTAL = 2,795.3

USE = 2,795.0

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

F.A.I. ROUTE 74
SECTION (20-1)RS-2
DEWITT COUNTY

SCALE: N/A
DATE: 02-25-08

DRAWN BY: CADD
CHECKED BY: