

**SUMMARY OF QUANTITIES**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10,92-8 HB-1BR	CHAMPAIGN	93	5

CONTRACT NO. 70695

CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - RURAL 20% STATE 80% FED X271-2A
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	12.0
•63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	2,050.0
•63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0
•63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4.0
63200310	GUARDRAIL REMOVAL	FOOT	2,103.0
63400105	GUARD POSTS	EACH	8.0
64200105	SHOULDER RUMBLE STRIP	FOOT	2,470.0
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	2,284.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12.0
67100100	MOBILIZATION	L SUM	1.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1.0
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	568.0
70300200	TEMPORARY PAVEMENT MARKING	FOOT	10,856.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3,808.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,860.0
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4.0
•78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,857.0
•78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	514.0
•78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72.0
•78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,116.0
•78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32.0
•78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8.0
•78200410	GUARDRAIL MARKERS, TYPE A	EACH	18.0
•78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32.0
•81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	100.0
•81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE). 1" DIA. <b>POLYETHYLENE</b>	FOOT	1,732.0
•81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,590.0
•83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	32.0
•83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	24.0
•84200800	POLE FOUNDATION, REMOVED	EACH	6.0
•84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6.0
X0323583	SPEED INDICATOR SIGN	CAL DA	396.0
X0932150	CURB AND GUTTER OUTLET, SPECIAL	EACH	16.0

CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - RURAL 20% STATE 80% FED X271-2A
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	424.0
Z0002005	ATTENUATOR BASE	SO YD	102.0
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULL REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2.0
Z0037300	PAVEMENT GROOVING	SO YD	254.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0

•SPECIALTY ITEM