

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10,92-8 HB-1)BR	CHAMPAIGN	93	7
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO. -		CONTRACT NO. 70695		

HMA SURFACE REMOVAL - BUTT JOINT

STATION TO STATION	SO. YD.
IL49 S	
306+23.50 TO 307+30.00	331.3
326+21.50 TO 326+81.50	186.7
1-74	
2294+00.00 TO 2296+35.00 WB	992.2
2294+00.00 TO 2296+38.00 EB	1,004.9
1001+85.00 TO 1003+85.00 WB	844.4
1001+78.00 TO 1003+85.00 EB	874.0
RAMP A	
STA. 401+00.00 TO 401+65.00	183.0
RAMP B	
300+15.00 TO 300+75.00	185.0
RAMP C	
STA. 501+00.00 TO 501+60.00	185.0
RAMP D	
100+09.50 TO 100+75.00	189.0
ACTUAL TOTAL	4,975.5
USED TOTAL	4,976.0

PAVEMENT REMOVAL

STATION TO STATION	SO. YD.
STA. 48+60.5 TO 49+07.2	114.2
STA. 50+92.7 TO 51+39.5	114.4
ACTUAL TOTAL	228.6
USED TOTAL	229.0

CURB & GUTTER REMOVAL

LOCATION	COMBINATION CURB & GUTTER REMOVAL	GUTTER REMOVAL
STATION TO STATION	FOOT	FOOT
RAMP A		
402+08.8 TO 402+91.0 LT & 402+09.2 TO 403+19.9 RT	266.0	
RAMP B		
298+61.9 TO 299+57.1 LT & 298+39.8 TO 299+43.4 RT	259.0	
RAMP C		
502+15.1 TO 503+24.0 LT & 502+05.5 TO 503+00.8 RT	275.0	
RAMP D		
98+43.3 TO 99+53.2 LT & 98+74.0 TO 99+53.2 RT	270.0	
47+88.24 TO 49+07.33 (LT & RT)		248.7
50+92.7 TO 52+18.5 (LT & RT)		262.6
ACTUAL TOTAL	1,070.0	511.3
USED TOTAL	1,070.0	512.0

APPROACH SLAB REMOVAL

STATION TO STATION	SO. YD.
49+07.2 TO 49+42.9	136.9
50+56.9 TO 50+92.7	141.2
ACTUAL TOTAL	278.1
USED TOTAL	279.0

ISLAND REMOVAL

LOCATION	SO. FT.
RAMP A	86.5
RAMP D	86.7
ACTUAL TOTAL	173.2
USED TOTAL	174.0

PAVED SHOULDER REMOVAL

STATION TO STATION	SO. YD.
41+01.60 TO 41+48.07 LT	26.2
307+74.34 TO 41+63.64 RT	59.3
306+43.60 TO 306+84.75	7.6
42+61.00 TO 42+95.40 LT	25.0
42+58.06 TO 43+13.61 RT	51.6
56+91.16 TO 57+41.92 LT	46.6
56+90.66 TO 57+37.68 RT	35.8
58+36.43 TO 58+91.08 LT	44.9
58+43.15 TO 59+00.00 RT	47.2
RAMP B	
299+57.07 TO 299+58.02 LT	0.5
299+43.40 TO 299+58.02 RT	16.1
RAMP C	
502+11.00 TO 502+15.19 LT	4.3
ACTUAL TOTAL	365.1
USED TOTAL	366.0

CONCRETE HEADWALL REMOVAL

STATION	EACH
RAMP B	
299+28.2 LT	1
RAMP C	
502+31.9 RT	1
RAMP D	
99+21.0 RT	1
ACTUAL TOTAL	3
USED TOTAL	3

PIPE CULVERT REMOVAL

STATION	FOOT
306+42 LT	20.0
306+63 RT	36.0
47+84 LT	44.0
47+84 RT	44.5
52+19 LT	50.4
52+19 RT	49.7
ACTUAL TOTAL	244.6
USED TOTAL	245.0

GUARDRAIL REMOVAL

STATION TO STATION	FOOT
IL-49S	
46+00 TO 54+00 LT & RT	1,600.0
1-74	
STA. 2296+09.3 TO 2297+07.8 RT, EB	98.8
STA. 2296+08.3 TO 2297+59.0 LT, EB	150.7
STA. 2296+83.6 TO 1002+00.1 RT, WB	150.2
STA. 2297+32.8 TO 1002+02.8 LT, WB	103.1
ACTUAL TOTAL	2,102.8
USED TOTAL	2,103.0

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION TO STATION	EACH
1-74	
2294+00 TO 1003+85 (WB)	16
2294+00 TO 1003+85 (EB)	16
ACTUAL TOTAL	32
USED TOTAL	32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: 06/2003

DRAWN BY: IYL
CHECKED BY: JH