

## SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI - 74  
CHAMPAIGN COUNTY  
LOCATION #1  
Sta. 898+76.00 to  
Sta. 903+82.00

FAI - 74  
VERMILION COUNTY  
LOCATION #2  
Sta. 1411+11.00 to  
Sta. 1416+17.00

Rural Multilane  
90%FED. 10%STATE  
J000-2A

Rural Multilane  
90%FED. 10%STATE  
J000-2A

CONSTRUCTION TYPE CODE:

<u>CODE NO.</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>QUANTITY</u>	<u>QUANTITY</u>
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	1,555.0	1,035.0	520.0
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	96.0	64.0	32.0
44201080	CLASS B PATCHES, TYPE IV	SQ YD	2,400.0	1,600.0	800.0
44213100	PAVEMENT FABRIC	SQ YD	4,050.0	2,700.0	1,350.0
44213200	SAW CUTS	FOOT	7,154.0	4,770.0	2,384.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20.0	12.0	8.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,450.0	2,300.0	1,150.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	28.0	14.0	14.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0
Z0017100	DOWEL BARS	EACH	840.0	560.0	280.0
Z0075300	TIE BARS	EACH	759.0	506.0	253.0
* SPECIALTY ITEMS					

FILE NAME = c:\projects\ad570703\70703plans.dgn	USER NAME = callierbx	DESIGNED - RTB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 74	SECTION 10-92-8,92-911	COUNTY •	TOTAL SHEETS 13	SHEET NO. 6
PLOT SCALE = 1/8" = 100.0000' / IN.	CHECKED -	DRAWN - JRP 12-07	REVISED -	SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	* CHAMPAIGN & VERMILION FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 70703		
PLOT DATE = 2/4/2008	DATE -		REVISED -							