

## SCHEDULE OF PATCH QUANTITIES

**LOCATION #2 - S.N. 092-0148**

CLASS B PATCHING											
BEGIN STATION	END STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 4 10.00 INCH 44200976 (SQ. YD.)	TYPE 2 15.00 INCH 44201031 (SQ. YD.)	TYPE 4 VARIABLE* 44201080 (SQ. YD.)	SAWCUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	DOWEL BARS Z0017100 (EACH)	PAVEMENT FABRIC 44213100 (SQ. YD.)
1411+11.00	1411+17.00	EBDL	6.0	12.0	-	8.0	-	48.0	3.0	10.0	8.0
1411+11.00	1411+17.00	EBPL	6.0	12.0	-	8.0	-	48.0	-	10.0	8.0
1411+17.00	1412+67.00	EBDL	150.0	12.0	-	-	200.0	336.0	75.0	30.0	200.0
1411+17.00	1412+67.00	EBPL	150.0	12.0	-	-	200.0	336.0	-	30.0	200.0
1412+67.00	1414+61.00	EBDL	194.0	12.0	258.7	-	-	424.0	97.0	60.0	258.7
1412+67.00	1414+61.00	EBPL	194.0	12.0	258.7	-	-	424.0	-	60.0	258.7
1414+61.00	1416+11.00	EBDL	150.0	12.0	-	-	200.0	336.0	75.0	30.0	200.0
1414+61.00	1416+11.00	EBPL	150.0	12.0	-	-	200.0	336.0	-	30.0	200.0
1416+11.00	1416+17.00	EBDL	6.0	12.0	-	8.0	-	48.0	3.0	10.0	8.0
1416+11.00	1416+17.00	EBPL	6.0	12.0	-	8.0	-	48.0	-	10.0	8.0
<b>CLASS B PATCH TOTALS</b>					517.3	32.0	800.0	2384.0	253.0	280.0	1349.4
USE					520.0	32.0	800.0	2384.0	253.0	280.0	1350.0

• VARIABLE DEPTH CLASS B PATCHES VARY IN DEPTH FROM 10 INCH TO 15 INCH AND ARE TO BE PAID FOR AS CLASS B PATCHING, TYPE IV. (SEE DETAIL SHEET NO. 12)

FILE NAME \*  
c:\projects\4578783\78783plans.dgn

USER NAME * collierbw	DESIGNED - RTB	REVISED -
	DRAWN - JRP	REVISED -
PLOT SCALE * 1/8" = 1' IN.	CHECKED -	REVISED -
PLOT DATE * 2/4/2008	DATE - 01-30-2008	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF PATCH QUANTITIES (LOCATION #2 - SN 092-0148)**

SCALE: NA SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 74	SECTION (10-92-8,92-9)I	COUNTY *	TOTAL SHEETS 13	SHEET NO. 10
* CHAMPAIGN & VERMILION			CONTRACT NO. 70703	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				